

Haryana Government Gazette EXTRAORDINARY

Published by Authority

© Govt. of Haryana

No. 78-2020/Ext.] CHANDIGARH, MONDAY, JUNE 8, 2020 (JYAISTHA 18, 1942 SAKA)

हरियाणा सरकार

स्थानीय शहरी निकाय विभाग

तथा

नगर तथा ग्रम आयोजना विभाग

अधिसूचना

दिनांक 8 जून, 2020

संख्या सी0 सी0 पी0 (एन0सी0आर0)/एफ.डी.पी./बी.डी.आर.-बी.सी.ए./2020/502.— हरियाणा नगरपालिका अधिनियम, 1973 (1973 का 24), की धारा 203 ग की उप—धारा (7), (नगर परिषद, बहादुरगढ़ की सीमाओं के भीतर आने वाले क्षेत्रों हेतु) तथा पंजाब अनुसूचित सड़क तथा नियंत्रित क्षेत्र अनियमित विकास निर्बन्धन अधिनियम, 1963 (1963 का पंजाब अधिनियम 41), की धारा 5 की उप—धारा (7) (नगर परिषद, बहादुरगढ़ की सीमाओं से बाहर आने वाले क्षेत्रों हेतु) द्वारा प्रदत्त शिक्तयों का प्रयोग करते हुए, तथा हरियाणा सरकार, शहरी स्थानीय निकाय विभाग तथा नगर तथा ग्राम आयोजना विभाग, अधिसूचना संख्या सी0 सी0 पी0 (एन0सी0आर0)/एफ.डी.पी./बी.डी.आर.—बी.सी.ए./2019/1923, दिनांक 16 सितंबर, 2019 के प्रतिनिर्देश से, हरियाणा के राज्यपाल, इसके द्वारा, अनुबन्ध ख में विनिर्दिष्ट नियंत्रित क्षेत्र को लागू और अनुबन्ध क तथा ख में दिये गये निर्बन्धनों तथा भार्तों सिहत बहादुरगढ़ के लिए अन्तिम विकास योजना—2041 ए०डी० प्रकाशित करते हैं।

डाईंग

- 1. विद्यमान भूमि उपयोग योजना ड्राईंग संख्या डी.टी.पी.(जे.एच.)/15/99, दिनांक 29 जून, 1999 (हरियाणा सरकार, नगर तथा ग्राम आयोजना विभाग, अधिसूचना संख्या सी.सी.पी.(एन.सी.आर.)/जे.सी.ए.—1/2003/2523, दिनांक 30 अक्टूबर, 2003, द्वारा हरियाणा राजपत्र दिनांक 30 अक्टूबर, 2003, में पहले ही प्रकाशित है)।
- 2. 13 जून, 2006 को प्रकाशित हरियाणा सरकार, राजपत्र अधिसूचना संख्या सी.सी.पी.(एन.सी.आर.)/जे.जे.आर./बी.जी.एच. /सी.ए.-4/ए/2006/1423, दिनांक 13 जून, 2006, द्वारा अधिसूचित बहादुरगढ़ की नगरपालिका सीमाओं के इर्द-गिर्द नियंत्रित क्षेत्र संख्या IV (भाग) के लिए विद्यमान भूमि उपयोग योजना ड्राईंग संख्या डी.टी.पी. (जे.एच.) 418/2012, दिनांक 02 फरवरी, 2012 |
- 3. अन्तिम विकास योजना—2041 ए.डी., बहादुरगढ़ के नियंत्रित क्षेत्र I, II, III, IV (भाग) ड्राईंग संख्या डी.टी.पी.(जे. एच.)620 / 2020, दिनांक 8, मई, 2020 |

अनुबन्ध क

बहादुरगढ़ के नियंत्रित क्षेत्र I, II, III, IV (भाग) अन्तिम विकास योजना, 2041 ए.डी. पर व्याख्यात्मक टिप्पण।

I ऐतिहासिक पृष्ठ भूमि:—

फरुख नगर के बहादुर खान तथा ताज मोहम्मद को 1755 ईस्वी में बहादुरगढ़ की सम्पदा 25 अन्य गावों के साथ जागीर में प्राप्त हुई थी। जब यह सम्पदा बहादुर खान तथा ताज मोहम्मद को सौंपी गई थी, तो नगर को सराफाबाद के नाम से जाना जाता था जिन्होंने 40 वर्ष से अधिक शासन किया तथा यहां पर एक किला बनवाया। यह शहर तथा इसके अधीन गांवों को लार्ड लैक द्वारा नवाब, झज्जर के भाई मोहम्मद इस्माईल खान को दान में दी गई, ईस्माईल खान के परिवार द्वारा सम्पदा को 1857 तक अधिकार में रखा गया तथा वर्ष 1860 में यह सम्पदा रोहतक जिले का हिस्सा बन गई।

II अवस्थिति तथा क्षेत्रीय प्रतिवेश:–

बहादुरगढ़ शहर दिल्ली हिसार राष्ट्रीय राजमार्ग संख्या ९ पर दिल्ली से 37 किलोमीटर की दूरी पर स्थित है। यह शहर 76°-55'-25" पूर्वी देशान्तर तथा 28°-43'-50" उत्तरी अक्षांश के बीच अवस्थित है। नजफगढ़ शहर तथा नांगलोई गांव, जो राष्ट्रीय राजधानी क्षेत्र (एन.सी.आर.) दिल्ली की मुख्य बस्तियां हैं, से कमशः 10 तथा 14 किलोमीटर की दूरी पर अवस्थित हैं। बहादुरगढ़ शहर दिल्ली तथा हरियाणा के मुख्य शहरों जैसे रोहतक, हिसार से राष्ट्रीय राजमार्ग संख्या ९ तथा रेलवे लाईन द्वारा भलीमांति जुड़ा हुआ है।

III भू–आकृति:–

भौगोलिक स्थिति अनुसार यह शहर नीचा तथा ढलान दक्षिण—पूर्व की तरफ है। पुरानी बस्ती दक्षिण—पूर्व की तरफ एक टिले पर स्थित है। इसके विकास का प्रभाव पश्चिम की तरफ राष्ट्रीय राजमार्ग के साथ, बहादुरगढ़—नजफगढ़ सड़क, बहादुरगढ़—झज्जर के साथ तथा उत्तर में रेलवे लाईन के पार है। पश्चिम जुआं नाला उत्तर से दक्षिण की तरफ शहर के मध्य से बहता हुआ दिल्ली में ड्रेन संख्या 8 में मिलता है। भूमिगत पानी खारा है तथा 2001 में नहरी पानी की आपूर्ति आरम्भ की गई है। यद्यपि, शहर नीचा है अतः यहां बाढ़ की आशंका बनी रहती है।

IV जनसांख्यिकी रूपरेखा:--

1991 की जनगणना अनुसार शहर की जनसंख्या 57235 व्यक्ति थी। इसकी जनसंख्या वृद्धि का पूर्व रूझान दर्शाता है कि दिल्ली के नजदीक होने पर भी खारे—भू—जल की स्थानीय समस्या तथा कमजोर शहरी अवसंरचना के कारण विकास दर प्राप्त नहीं कर सका।

बहादुरगढ़ शहर की दशकवार 1961 जनसंख्या निम्नानुसार है:--

बहादुरगढ़ शहर की जनसंख्या

वर्ष	जनसंख्या दशक में	प्रतिशत वृद्धि दर
1961	14,982	_
1971	25,812	72.28
1981	37,488	45.23
1991	57,235	52.67
2001	1,31,925 (शहरी क्षेत्र में गांव की आबादी को मिलाते हुए)	150.62
2011	1,84,540	39.90

अनुमानित वृद्धि दर निम्नानुसार होगी:-

वर्ष	जनसंख्या	वृद्धि दर
2011-2021	2,91,573*	58 प्रतिशत
2021-2031	4,63,600*	59 प्रतिशत
2031-2041	7,37,124 अर्थात् (7,37,000)*	59 प्रतिशत

^{*} अनुमानित जनसंख्या

V आर्थिक विशेषताएं:--

शहर में नहरी पानी की आपूर्ति होने से खारे पानी की मुख्य का समाधान हो गया है। जिसके परिणामस्वरूप, अब शहर के औद्योगिक विकास में बढ़ोतरी हुई हैं। माननीय सर्वोच्च न्यायालय के आदेशानुसार दिल्ली शहर से अननुरूप क्षेत्र में स्थित औद्योगिक ईकाईयों के निकाले जाने से तथा बहादुरगढ़ शहर दिल्ली के नजदीक होने के कारण पुर्नस्थापना उपरान्त शहर के औद्योगिक आधार में बढ़ोतरी हुई है।

भि उपयोग प्रस्ताव

बहादुरगढ़ शहर की जनसंख्या 2041 ईस्वी तक 7.37 लाख प्रस्ताव की जनसंख्या हेतु विकसित किए जाने के लिए प्रस्तावित है। विभिन्न भूमि उपयोगों का विवरण निम्न प्रकार से दिया गया है:-

क्रम संख्या	भूमि उपयोग	कुल क्षेत्र (हेक्टेयर में)	कुल क्षेत्र की प्रतिशता
1.	रिहायशी	2356	39.17
2.	वाणिज्यिक	270	4.49
3.	औद्योगिक	1104	18.36
4.	परिवहन तथा संचार	772	12.84
5.	जन उपयोगिताएं	230	3.83
6.	सार्वजनिक तथा अर्ध—सार्वजनिक उपयोगिताएं	287	4.77
7.	पार्क तथा खुले स्थान	994	16.54
	कुल	6013	100.00

मौजूदा शहर एवं शहरी क्षेत्र में पड़ने वाले गांवो का क्षेत्र – 252 हेक्टेयर।

विभिन्न भूमि उपयोगों का विवरण

1 रिहायशी:-

बहादुरगढ़ शहर की अन्तिम विकास योजना—2041 ए.डी. 7.37 लाख की अनुमानित जनसंख्या हेतु डिजाईन की गई है। इस योजना में 2356 हेक्टैयर भूमि में रिहायशी क्षेत्र के लिए आरक्षित की गई है। सेक्टर संख्या 2, 6, 7, 9, 9ए, 10, 11, 13, हरियाणा शहरी विकास प्राधिकरण द्वारा पहले ही विकसित किए जा चुके है। इसके अतिरिक्त, सेक्टर संख्या 3, 3ए, 4ए, 14, 15, 28, 28ए, 29, 35, 36, 37, में रिहायशी प्लाटिड / ग्रुप हाउसिंग कालोनी विकसित करने के लिए अनुज्ञप्तियां जारी की गई है। प्रत्येक आवासीय क्षेत्र को दोनों तरफ 20 प्रतिशत भिन्नता के साथ ड्राईंग में दर्शाई गई सेक्टर सघनता तथा इसके अतिरिक्त नई एकीकृत अनुज्ञापन पॉलिसी (एनआईएलपी), दीन दयाल जन आवास योजना नीति (डीडीजेएवाई) तथा अफोर्डऐबल ग्रुप हारुसिंग पॉलिसी में यथा विहित सघनता में विकसित किया जाएगा। 20 प्रतिशत ग्रुप हारुसिंग कम्पोनेन्ट पॉलिसी रिहायशी क्षेत्र में भी लागू होगी।

सघनता की वृद्धि हेतू उपरोक्त के अतिरिक्त, विकास योजना में निम्नलिखित प्रावधान भी किये गये है :--

- (क) अतिरिक्त आबादी की आवश्यकता को पूरा करने के लिए पहले से ही योजनाबद्ध / विकसित आवासीय क्षेत्रों में अवसंरचना के लिए अतिरिक्त क्षेत्र उपलब्ध करवाया जाएगा।
- (ख) आवासीय कॉलोनी / सेक्टर में सडकों की न्यनतम चौडाई 12 मीटर से कम नहीं होगी।
- (ग) आवासीय कॉलोनी/सेक्टरों में पार्क/खुले स्थानों के लिए न्यूनतम क्षेत्र इस रीति में योजनाबद्ध किया जाएगा कि यह प्रति व्यक्ति 2.5 वर्ग मीटर के न्यूनतम मापदंड को पूरा करेगा।

२ वाणिज्यिक:-

बहादुरगढ़ शहर की वाणिज्यिक आवश्यकताओं की पूर्ति हेतु वाणिज्यिक प्रयोजनों के लिए 270 हेक्टेयर का क्षेत्र आरक्षित किया गया है। ऑटो मार्किट राष्ट्रीय राजमार्ग—9 के साथ—साथ अनियोजित तरीके से विकसित है, जिससे ट्रैफिक जाम तथा दुर्घटनाएँ होती है। इस समस्या को हल करने के लिए ऑटो मार्किट को सेक्टर 12 में एक नए स्थान पर स्थानांतरित करने की प्रस्तावना है। शहर के मध्य में सेक्टर 4 वाणिज्यिक उपयोग हेतु आरक्षित किया गया है। इसके अतिरिक्त, सेक्टर 9, 12, 27, 35, 36, 38, 44 में वाणिज्यिक पॉकेट प्रस्तावित की गई हैं। इसके अतिरिक्त, प्रत्येक सेक्टर को पड़ोस योजना अवधारणा पर विकसित किया जाएगा तथा प्रत्येक सेक्टर की स्थानीय वाणिज्यिक जरूरतों को स्थानीय शोपिंग केन्द्र विकसित करते हुए उन्हीं सेक्टरों में पूरा किया जायेगा।

3 औद्योगिक:--

इस अन्तिम विकास योजना में, दिल्ली से औद्योगिक संस्थानों के स्थानांतरण के कारण औद्योगिक भूमि की उच्च मांग को देखते हुए औद्योगिक उपयोग के अधीन कुल 1104.00 हेक्टेयर कुल क्षेत्र प्रस्तावित है। सेक्टर 4बी, 16, 17, 19 भाग, 21, 22, हिरयाणा शहरी विकास प्राधिकरण / हिरयाणा राज्य औद्योगिक अवसंरचना विकास परिषद द्वारा पहले ही विकसित किए जा चुके है। इसके अतिरिक्त सेक्टर संख्या 18, 18ए, 20 भाग, 23, 24 भाग, 33, 34, तथा 43 भी औद्योगिक प्रयोजन के लिए प्रस्तावित है।

4 परिवहन और संचार:-

इस अन्तिम विकास योजना 2041 ईस्वी में, 772.00 हैक्टेयर क्षेत्र परिवहन और संचार उपयोग के लिए प्रस्तावित किया गया है। 75 मीटर चौड़ी वी—1 बाईपास सड़क जो सेक्टर 9, राष्ट्रीय राजमार्ग संख्या 9 से शुरू होकर राष्ट्रीय राजमार्ग संख्या 9 नजदीक सेक्टर 33 तक है, पहले ही विकसित की जा चुकी हैं तथा कार्यशील है। यातायात के सहज सुचारू प्रवाह हेतु दूसरी उत्तरी परिधीय सड़क (वी—2ए) 60 मीटर चौड़ी, जो दिल्ली सीमा से शुरू होकर सेक्टर 23, 24, 44, 49, 50, 51, 47, 48 तथा 31 के ऊपर से होती हुई तथा राष्ट्रीय राजमार्ग संख्या 9 पर नजदीक गांव जाखैदा पर मिलती है, भी प्रस्तावित है। इंट्रा सिटी यातायात के लिए ग्रिंड आयरन पैटर्न पर 60 मीटर तथा 45 मीटर चौड़ी सड़कों का नेटवर्क प्रस्तावित किया गया है। मैट्रो रेल का निर्माण पहले ही किया जा चुका है और यह सेक्टर 6 तक कार्यात्मक है। इस विकास योजना के अधीन उत्तरी भाग में राजमार्ग संख्या—9 के साथ मेटो रेल को नियंत्रित क्षेत्र की सीमा तक प्रस्तावित किया गया है।

बहादुरगढ़ मूल रूप से एक औद्योगिक शहर है। सेक्टर 17ए में 47 हैक्टेयर क्षेत्र रेलवे यार्ड, रेलवे स्टेशन और साईडिंग, सड़कें और परिवहन डिपो और पार्किंग क्षेत्र हेतु प्रस्तावित किया गया है। सेक्टर 38 में 19.0 हैक्टेयर का क्षेत्र परिवहन और संचार प्रयोजनों के लिए प्रस्तावित किया गया है। अंतिम विकास योजना बहादुरगढ़ —2031 ईस्वी में पहले सेक्टर 32 परिवहन और संचार क्षेत्र के लिए आरक्षित था जिसे अब औद्योगिक प्रयोजन और क्षेत्र की क्षमता की बढ़ती मांग को देखते हुए औद्योगिक क्षेत्र के रूप में प्रस्तावित किया गया है। 89.50 हैक्टेयर क्षेत्र सेक्टर 33 के पश्चिम दिशा में, सेक्टर 32 के रूप में परिवहन और संचार उपयोग के लिए प्रस्तावित किया गया है। मुख्य सड़क के रास्ता अधिकार की श्रेणीबद्धता नियमानुसार प्रस्तावित है:—

क्रम संख्या	वर्गीकरण	सड़कों का नाम	भूमि आरक्षण
सख्या			
1.	वी—1	बाईपास	दोनों तरफ 100 मीटर चौड़ी हरित पट्टी के साथ 75 मीटर चौड़ी सड़क।
2.	वी—1ए	रोहतक–दिल्ली राष्ट्रीय राजमार्ग संख्या 9	दोनों ओर 60 मीटर चौड़ी हरित पट्टी सहित वर्तमान चौड़ाई।
3.	वी—2	सेक्टर विभाजक सड़क	60 मीटर चौड़ी सड़क।
4.	वी—2ए	परिधीय सड़क	दोनों ओर 30 मीटर चौड़ी हरित पट्टी सहित 60 मीटर चौड़ाई।
5.	वी—2बी	परिधीय सड़क	बाहरी ओर 30 मीटर चौड़ी हरित पट्टी सहित 60 मीटर चौड़ाई।
6.	वी— 2सी	बहादुरगढ़—झज्जर, बहादुरगढ़—बेरी, बहादुरगढ़ —सिद्धीपुर, बहादुरगढ़—बादली सड़क	दोनों ओर 30 मीटर चौड़ी हरित पट्टी सहित 60 मीटर चौड़ाई।
7.	वी—3	सेक्टर विभाजक सड़क	45 मीटर चौड़ी सड़क।
8.	वी—३ए	बहादुरगढ़—नजफगढ़, बहादुरगढ़—नाहरा सड़क	वर्तमान चौड़ाई को 45 मीटर चौड़ाई करना प्रस्तावित ।
9.	वी—3बी	सेक्टर विभाजक सड़क	30 मीटर चौड़ी सड़क (विकसित सड़क)

जन उपयोगिता अंचल:-

7.37 लाख की प्रस्तावित आबादी की जरूरतों को पूरा करने के लिए 230.00 हैक्टेयर भूमि जन उपयोगी सुविधाओं हेतु आरिक्षत की गई है। जन उपयोगी सुविधाओं के अधीन आरिक्षत क्षेत्र सेक्टर 7, 17, 22ए, 23, 30, 33, 36, 37, 38, 44 तथा 49 तथा कृषि अंचल में प्रस्तावित किया गया है। इससे पहले, अंतिम विकास योजना बहादुरगढ़ 2031 ईस्वी में सेक्टर—29 से परे, सार्वजनिक उपयोगिता क्षेत्र के लिए एक पॉकेट आरिक्षत की गई थी जिसे अब बेहतर नियोजन के लिए आवासीय उपयोग के लिए योजनाबद्ध किया गया है।

6 सार्वजनिक और अर्ध—सार्वजनिक अंचल:–

राष्ट्रीय राजधानी क्षेत्र के क्षेत्रीय योजना में, बहादुरगढ़ शहर को दिल्ली महानगरीय क्षेत्र के शहर के रूप में चिहिनत किया गया तथा उपरोक्त योजना की सिफारिशों अनुसार बहादुरगढ़ शहर में राष्ट्रीय राजधानी के भार को कम करने के लिए दिल्ली से विस्थापित होने वाले सार्वजनिक तथा निजी उपक्रमों के कार्यालय तथा संस्थानों को समायोजित किया जाएगा। उपरोक्त प्रस्तावना को ध्यान में रखते हुए, अन्तिम विकास योजना में 287.00 हैक्टेयर क्षेत्र सार्वजनिक तथा अर्ध—सार्वजनिक उपयोग के लिए प्रस्तावित किया गया है। यह सार्वजनिक तथा अर्ध—सार्वजनिक प्रयोग शहरी स्तर की सामुदायिक सुविधाएं जैसे तकनीकी महाविद्यालय, तकनीकी प्रशिक्षण संस्थान, चिकित्सीय संस्थान, अस्पताल, अग्निशमन केन्द्र तथा सरकारी कार्यालय इत्यादि समायोजित किए जाएंगे। सार्वजनिक तथा अर्ध—सार्वजनिक उपयोग के अधीन आरक्षित क्षेत्र सेक्टर 3ए, 5, 7, 10, 12, 13, 14, 19, 30, 31, 38, 45 तथा 50 में प्रस्तावित किया गया है।

7 खुले स्थान और हरित पटि्टयां-

कुल 994.00 हैक्टेयर क्षेत्र को खुले स्थान और हरित पिट्टयों के लिए प्रस्तावित किया गया है। सेक्टर 5 (भाग) में 37 हैक्टेयर भूमि शहरी स्तर के पार्क के लिए चिहिनत की गई है। कमशः सेक्टर 7 तथा 11 में 7.00 हैक्टेयर तथा 5.00 हैक्टेयर क्षेत्र पार्क के लिए प्रस्तावित है। सेक्टर 11 में 6 हैक्टेयर क्षेत्र स्टेडियम तथा खेल मैदान के लिए प्रस्तावित किया गया है। सेक्टर 39, 12ए तथा 22ए भाग भी खुले स्थान के लिए आरक्षित है। सेक्टर 44 तथा 46 में भी 9.00 हैक्टेयर तथा 13.00 हैक्टेयर भूमि कमशः पार्क, खेल मैदान, स्टेडियम के लिए प्रस्तावित है। सेक्टर 37 में हरियाणा शहरी विकास प्राधिकरण की अर्जित भूमि में एक 2 हैक्टेयर का क्षेत्र स्टेडियम के लिए प्रस्तावित किया गया है। इसके अतिरिक्त, सडकों, रेलवे लाईन, नालों/नहर के साथ—साथ भी हरित पट्टियां जैसा कि प्लान में दर्शाया है, प्रस्तावित की गई है।

जल संरक्षण / प्राकृतिक संरक्षण अंचल क्षेत्र:—

प्राकृतिक संरक्षण क्षेत्र (एन.सी.जैड) प्रमुख प्राकृतिक विशेषताएं हैं, जिन्हें क्षेत्रीय योजना 2021 ई. में पर्यावरण के प्रति संवेदनशील क्षेत्रों के रूप में पहचाना जाता है, जिसमें कृषि और बागवानी, मछली पालन, सामाजिक वानिकी, वनीकरण तथा क्षेत्रीय मनोरजंक कियाएं निर्माण सिहत अनुज्ञेय गतिविधियों के 0.5 प्रतिशत से अधिक नहीं होनी चाहिए। प्राकृतिक संरक्षण जोन की पहचान करने के लिए ग्राउंड टरूथिंग एक्सरसाईज कार्यान्वित की जा रही है। इसके अलावा, मामला 2014 की ओ.ए. संख्या 147 शीर्षक विधिक सहायता सिमित एन.जी.टी. बार एसोसियेशन बनाम एम ओई एफ तथा अन्य के रूप में माननीय राष्ट्रीय हरित अधिकरण में विचाराधीन है। इसलिए माननीय एन.जी.टी. के आदेश 20.11.2019 और 20.03.2020 और बाद के किसी भी निर्णय पर, एन.सी.जैड. के मामले में लागू होंगे। और यदि किसी साइट को एन.सी.जैड के रूप में अंतिम रूप दिया जाता है, तो एन.सी.जैड के प्रावधान योजना में दिए गए प्रस्तावों के बावजूद उस क्षेत्र पर लागू होंगे।

9 कृषि अचंल:-

नियंत्रित क्षेत्र में शेष क्षेत्र कृषि अंचल के रूप में रखा गया है। तथापि, यह इस क्षेत्र में आवश्यक भवन विकास को नहीं रोकंगा, जैसे आबादी देह के साथ—साथ मौजूदा गांवों का विस्तार, यदि सरकार द्वारा प्रायोजित या अनुमोदित किसी परियोजना के रूप में किया जाना है और अनुबन्ध 'ख' में, परिशिष्ट 'ख' के अधीन अंचल विनियमों में अनुमत गतिविधियों के रूप में शामिल है और सम्बन्द्ध सुविधाओं के रखरखाव और कृषि क्षेत्र के रूप में सुधार के लिए जरूरी सुविधाएं जो शहर के लिए एक खुले ग्रामीण परिवेश के रूप में सेवा करने हेतु प्रस्तावित है। लगभग 10 हैक्टेयर क्षेत्र डेरी फार्मिंग के लिए ईयरमार्क किया गया है, जो सिद्धिपुर सड़क पर पुराने शहर से स्थानांतरित की जानी है।

अंचल विनियमन

भूमि उपयोग सम्बन्धी प्रस्तावों को अंचल विनियम (अनुबन्ध ख) बनाते हुए वैध बनाया जा रहा है जो इस विकास योजना का हिस्सा होंगे। ये विनियम भूमि उपयोग में परिवर्तन और विकास के मानकों को शासित करेंगे। इनमें सम्बद्ध तथा सहायक उपयोगों का भी विस्तारपूर्वक वर्णन किया जाएगा जो विभिन्न मुख्य भूमि उपयोगों में अनुमत किए जाएंगे तथा नियतन करेंगे कि भूमि उपयोग के सभी परिवर्तन तथा विकास, विकास तथा उचित नियन्त्रण को निर्दिष्ट करने के लिए प्रत्येक क्षेत्र के लिए विस्तृत सेक्टर योजनाएं तैयार करना सुनिश्चित करने के लिए सेक्टर योजना में दर्शाए गए ब्यौरों के अनुसार होगा।

अनुबन्ध ख

ड्राईंग संख्या डी० टी० पी० (जे०एच०) 620 / 20, दिनांक 8 मई, 2020 अन्तिम विकास योजना में दर्शाए अनुसार बहादुरगढ़ के नियंत्रित क्षेत्रों में भूमि का उपयोग तथा विकास शासित करना।

I. सामान्यः–

- (1) बहादुरगढ़ के नियंत्रित क्षेत्रों के लिए विकास योजना का भाग बनने वाले ये अंचल विनियम बहादुरगढ़ के नियंत्रित क्षेत्रों के लिए विकास योजना के अंचल विनियम कहे जायेंगे।
- (2) इन विनियमों की अपेक्षाएं विकास योजना में शामिल समूचे क्षेत्र के लिए होंगी तथा पंजाब अनुसूचित सड़क तथा नियंत्रित क्षेत्र अनियमित विकास निर्बन्धन अधिनियम, 1963 (1963 का पंजाब अधिनियम 41) तथा हरियाणा नगरपालिका अधिनियम, 1973 (1973 का 24) और उसके अधीन बनाये गये नियमों की अपेक्षाओं के अतिरिक्त होंगी।

II. परिभाषायें:-

इन विनियमों में;--

- (क) "अनुमोदित" से अभिप्राय है, सक्षम प्राधिकारी द्वारा अनुमोदित;
- (ख) "भवन नियमों" से अभिप्राय हैं, नियमों के भाग-VII में अन्तर्विष्ट नियम; '
- (ग) ''ड्राईंग'' से अभिप्राय है, ड्राईंग संख्या डी.टी.पी. (जे.एच.) 620 / 20, दिनांक ८ मई, 2020.
- (घ) "भवन संहिता" से अभिप्राय है, हरियाणा भवन संहिता, 2017;

(ड.) "फर्श क्षेत्र अनुपात" से अभिप्राय है, सभी मंजिलों के कुल आच्छादित क्षेत्र तथा सौ के गुणक को प्लाट क्षेत्र से विभाजित करते हुए प्राप्त किया गया भागफल, अर्थात् :--

फर्श क्षेत्र अनुपात = <u>कुल आच्छादित क्षेत्र</u> x 100 प्लाट क्षेत्र

फर्श क्षेत्र अनुपात की गणना के प्रयोजन के लिए, कैंटिलीवर अनुमत छत प्रोजेक्शनों; लिफ्ट कमरा, ममटी, छज्जा, तहखाना या कोई फर्श यदि पार्किंग, सेवाओं और मंडारण, केवल पार्किंग/पैदल यात्री प्लाजा के लिए उपयोग हेतु प्रस्तावित स्टिलट क्षेत्र, (खुला), खुली सीढ़ी (ममटी के बिना), पहुँच के साथ या के बिना, छत अग्नि सीढ़ी, अलिंद पानी की टंकी, अनुमत आकार के खुला आंगन के लिये उपयोग किया गया है, फर्श क्षेत्र अनुपात में गिना नहीं जाएगाः

परंतु स्टिलट से अगली मंजिल तक शाफ्ट, शूटस, लिफ्ट वैल तथा सीढ़ी के अधीन क्षेत्र, भूमि तल से फर्श क्षेत्र अनुपात केवल एक बार गिना जाएगाः

परंतु यह और कि यदि वेंटिलेशन शाफ्ट क्षेत्र तीन वर्ग मीटर से अधिक है, तो यह फर्श क्षेत्र अनुपात में नहीं गिना जाएगा;

- (च) 'ईंधन स्टेशन' से अभिप्राय है, ईंधन भरने वाला स्टेशन जो ऑटोमोबाइल के लिए ईंधन की खुदरा आपूर्ति प्रदान करता है, जिसमें पैट्रोल पम्प, सी. एन. जी. स्टेशन, जैव–ईंधन, चार्जिंग स्टेशन, बैटरी उपलब्ध स्टेशन आदि शामिल हैं:
- (छ) "वर्ग आवास" से अभिप्राय है, रिहायशी प्रयोजन के लिए फ्लैटों के रूप में डिजाईन तथा विकसित किये गये भवन या वर्ग आवास का अनुषंगी कोई भवन;
- (ज) ''हल्के उद्योग'' से अभिप्राय है, ऐसा उद्योग जिसके कारण हानिकारक या घृणाजनक शोर, धुआं, गैस, भाप गन्ध, धूल, बिहःस्राव और कोई अन्य अत्यधिक डिग्री का प्रदूषण न हो और बिजली द्वारा चालित हों;
- (झ) "स्थानीय सेवा उद्योग" से अभिप्राय है, ऐसा उद्योग जिसका विनिर्मित माल और उत्पादन प्रायः स्थानीय क्षेत्र के भीतर उपभोग किया जाता हो, उदाहरणार्थ बेकरियां, आईसक्रीम विनिर्माण, वातित जल, बिजली से चलने वाली आटे की चिक्कयां, लोंड्री, ड्राईक्लीनिंग और रंगाई, स्वचालित गाड़ियों, स्कूटर तथा साईकलों की मुरम्मत तथा सर्विस, घरेलू बर्तनों की मुरम्मत, जूते बनाना और उनकी मुरम्मत, ईंधन डिपो आदि बशर्ते कि उनमें किसी ठोस ईंधन का प्रयोग न किया जाता हो:
- (ञ) ''मध्यम उद्योग'' से अभिप्राय है, हल्का उद्योग तथा स्थानीय सेवा उद्योग के अलावा सभी उद्योग और जो घृणाजनक और खतरनाक गंध तथा दुर्गन्ध न फैलाते हों;
- (ट) ''व्यापक उद्योग'' से अभिप्राय है, ऐसा उद्योग जो सरकार की अनुमित से स्थापित किया जाये और जो व्यापक हो, जिसमें 100 से अधिक कामगार नियुक्त हों तथा जिसमें ईंधन चालित शक्ति का प्रयोग किया जाये बशर्ते कि इसमें किसी प्रकार के हानिकारक तत्व न हों;
- (ठ) "भारी उद्योग" से अभिप्राय है, सरकार की अनुमित से सार्वजनिक या अर्धसार्वजनिक या निजी क्षेत्र में स्थापित किया गया उद्योग (प्लान्ट, मशीनरी इत्यादि की लागत जैसा कि सरकार की उद्योग नीति में परिभाषित हो);
- (ड) ''घृणाजनक या परिसंकटमय उद्योग'' से अभिप्राय है, सरकार की अनुमित से स्थापित किया गया उद्योग और जिसमें अत्यधिक पूंजी लगी हो। जिसमें अत्यधिक धुंआ, शोर, स्पन्दन, दुर्गन्ध, अप्रिय या हानिकारक बिहःस्राव, विस्फोटक, ज्वलनशील सामग्री इत्यादि और समुदाय के स्वास्थ्य और सुरक्षा के लिए अन्य खतरनाक तत्त्व शामिल हों:
- (ढ) ''वास्तविक तिथि'' से अभिप्राय है, नीचे घोषित किए गए विभिन्न नियंत्रित क्षेत्रों की अधिसूचना के प्रकाशन की तिथि;

क्रम संख्या	नियंन्त्रित क्षेत्र का नाम तथा अधिसूचना संख्या	वास्तविक तिथि
1	पंजाब सरकार राजपत्र अधिसूचना संख्या 3959—2टी.सी.पी.—64/29556, दिनांक 07 नवम्बर, 1964 द्वारा अधिसूचित बहादुरगढ़ नगरपालिका के ईर्द—गिर्द नियंत्रित क्षेत्र जिसका हरियाणा सरकार राजपत्र में दिनांक 26 फरवरी, 1965 को प्रकाशन हुआ।	26 फरवरी, 1965
2	हरियाणा सरकार राजपत्र अधिसूचना संख्या ४७७९–१०डी.पी.–८४/९७२०, दिनांक २५ जून १९८४ द्वारा अधिसूचित बहादुरगढ़ के ईर्द–गिर्द नियंत्रित क्षेत्र जिसका हरियाणा सरकार राजपत्र में दिनांक १० जूलाई, १९८४ को प्रकाशन हुआ।	10 जुलाई, 1984

क्रम संख्या	नियंन्त्रित क्षेत्र का नाम तथा अधिसूचना संख्या	वास्तविक तिथि
3	हरियाणा राजपत्र दिनांक 18 जून, 1996 में प्रकाशित हरियाणा सरकार राजपत्र अधिसूचना संख्या सी.सी.पी.(एन.सी.आर)—96 / 8681, दिनांक 12 जून, 1996 द्वारा अधिसूचित अतिरिक्त नियंत्रित क्षेत्र संख्याा—III बहादुरगढ़।	18 जून, 1996
4	हरियाणा राजपत्र दिनांक 13 जून, 2006 में प्रकाशित अधिसूचना संख्या सी. सी.पी.(एन.सी.आर)/जे.जे.आर./बी.जी.एच./सी.ए.—प्ट/ए/2006/1423, द्वारा अधिसूचित बहादुरगढ़ नगरपालिका सीमा के ईर्द–गिर्द नियंत्रित क्षेत्र ।	13 जून, 2006

- (ण) नियंत्रित क्षेत्र में किसी भूमि अथवा भवन के संबंध में ''अननुरूप उपयोग'' से अभिप्राय है, ऐसी भूमि अथवा भवन जो विकास योजना में क्षेत्र के उस भाग के लिए विनिर्दिष्ट मुख्य भूमि उपयोग के विपरीत हो;
- (त) "सार्वजनिक उपयोगिता सेवा भवन" से अभिप्राय है, ऐसा भवन जो सार्वजनिक उपयोगिता सेवाओं को चलाने के लिए अपेक्षित हो, जैसे जल–सप्लाई, जल निकास, बिजली, डाक तथा तार तथा परिवहन तथा दमकल केन्द्र सहित कोई नगरपालिका सेवा;
- (थ) "नियमों" से अभिप्राय है, पंजाब अनुसूचित सड़क तथा नियंत्रित क्षेत्र अनियमित विकास निर्बन्धन नियम, 1965; तथा हरियाणा नगरपालिका अधिनियम, 1973 के अधीन बनाये गये नियम;
- (द) "सेक्टर सघनता" और "कॉलोनी सघनता", "नगर नियोजन स्कीम सघनता" से अभिप्राय है, उस सेक्टर क्षेत्र तथा कॉलोनी क्षेत्र, जैसी भी स्थिति हो, में प्रति व्यक्तियों की संख्या;
- (ध) "सेक्टर क्षेत्र, कॉलोनी क्षेत्र' अथवा "नगर नियोजन स्कीम क्षेत्र" से अभिप्राय है, ड्राईंग में दर्शाया गया तथा/या सेक्टर/कॉलोनी/स्कीम की अनुमोदित अभिन्यास में दर्शाए अनुसार मुख्य सड़क प्रणाली के भीतर यथा परिबद्ध, सेक्टर का या कॉलोनी या स्कीम का क्षेत्रः

व्याख्या:-

- (1) इस परिभाषा में ''सेक्टर क्षेत्र'' ''कालोनी क्षेत्र'' तथा "नगर नियोजन स्कीम क्षेत्र" से अभिप्राय है, सेक्टर या कालोनी का क्षेत्र जो कालोनी/सेक्टर/नगर नियोजन स्कीम क्षेत्र की ड्राईंग में तथा अनुमोदित अभिन्यास योजना पर दर्शाया गया है जिसमें सेक्टर या कालोनी/नगर नियोजन स्कीम क्षेत्र, जैसे भी स्थिति हो, में भवन विकास के लिए अनुपयुक्त क्षेत्र शामिल नहीं है;
- (2) मुख्य सड़कों तथा उनकी निकटवर्ती हरित पटि्टयों के अधीन आने वाले क्षेत्र के 50 प्रतिशत का लाभ, यदि कोई हो, प्लाटिड / ग्रुप हाऊसिंग कालोनी की दशा में प्लॉटेबल क्षेत्र / फर्श क्षेत्र अनुपात हेतु अनुमत किया जाएगा।
- (3) औद्योगिक स्कीम/सेक्टर /स्कीम से भिन्न, नगर नियोजन स्कीम कालोनी या सेक्टर की विन्यास योजना में, सड़कों, खुले स्थानों, विद्यालयों, सार्वजनिक तथा सामुदायिक भवन तथा अन्य सामूहिक उपयोगों के लिए आरक्षित भूमि, नगर नियोजन स्कीम/कालोनी/सेक्टर के अधीन भूमि के कुल क्षेत्र के 45 प्रतिशत से कम नहीं होगी।
- (4) सेक्टर सघनता या कालोनी सघनता की संगणना के प्रयोजनों के लिए यह माना जायेगा कि सेक्टर क्षेत्र या कालोनी क्षेत्र का 55 प्रतिशत आवासीय प्लाटों के लिए उपलब्ध होगा जिसमें ग्रुप आवास के अधीन क्षेत्र भी शामिल होगा तथा प्रत्येक भवन प्लाट औसतन प्रत्येक तीन निवास ईकाइयों में 4.5 व्यक्ति प्रति निवास ईकाई या 13.5 व्यक्ति भवन प्लाट या कालोनी/ग्रुप आवास समूह की अंचल योजना में यथा सम्मिलित होगा। यद्यपि, दुकान तथा आवासीय प्लाट के मामले में केवल एक निवास इकाई मानी जायेगी;
- (5) उपरोक्त दी गई किसी बात के होते हुए भी, विनिर्दिष्ट पॉलिसी जैसे नई एकीकृत अनुज्ञापन पॉलिसी; के अधीन अनुमोदित परियोजनाएं , प्लॉटऐबल क्षेत्र की बजाय फर्श क्षेत्र अनुपात तथा सघनता पैरामीटर से शासित होंगी;
- (न) "स्थल आच्छादन" से अभिप्राय है, भवन के भूतल क्षेत्र और स्थल क्षेत्र द्वारा आच्छादित क्षेत्र के बीच प्रतिशतता में अभिव्यक्त अनुपात;
- (प) "अधिनियम", "कालोनी", "उप—िनवेशक", "विकास योजना", "सेक्टर" "स्कीम" और "सेक्टर योजना" शब्दों का वहीं अर्थ होगा, जो उन्हें पंजाब अनुसूचित सड़क तथा नियंत्रित क्षेत्र अनियमित विकास निर्बन्धन अधिनियम, 1963 (1963 का पंजाब अधिनियम 41) और नियम, 1965 तथा हिरयाणा नगरपालिका अधिनियम, 1973 (1973 का 24) इसके अधीन बनाए गए नियमों में उन्हें दिया गया है;

- (फ) "फार्म गृह" से अभिप्राय है, किसी फार्म के स्वामी द्वारा अपनी भूमि पर निम्नलिखित प्रयोजनार्थ निर्मित घर है—
 - (i) निवास यूनिट अर्थात् मुख्य उपयोगः; तथा
 - (ii) फार्म छायाबान अर्थात् गौण उपयोग।

टिप्पण:-

- (1) फार्म गृह का निर्माण "कृषि अंचल में आबादी देह से बाहर फार्म गृहों की व्यवस्था'' संबंधी खण्ड XIX के अधीन दिये गये निर्बन्धनों से शासित होगा:
- (2) "फार्म शैड" ''भवन नियंत्रण और स्थल विशिष्टियों'', के सम्बन्ध में खंड XIX में उल्लिखित निर्बन्धनों द्वारा शासित होंगे।
- (ब) "टांड या पुश्तवान" से अभिप्राय है, कमरे के अन्दर बनाए गए अनुलम्ब खम्भे को छोड़कर, किसी भी स्वरूप की शैल्फ जैसे बहिर्गत भाग, बशर्ते जिसका बर्हिगत भाग एक मीटर से अधिक चौड़ा न हो ;
- (भ) "अटारी" से अभिप्राय है, अधिकतम 1.5 मीटर की ऊँचाई सहित अवशिष्ट स्थल पर दो मंजिलों के बीच का मध्यवर्ती स्थल तथा जो केवल भंडारण प्रयोजन हेत् निर्मित की गई है अथवा अपनाई गई है;
- (म) "परछती तल" से अभिप्राय है, निम्न मंजिल का 1/2 (आधा) तक के सीमित क्षेत्र सहित तथा न्यूनतम ऊँचाई 2.3 मीटर सहित दो मंजिलों के बीच कोई मध्यवर्ती तल और ऊपरी तल स्तर से 2.3 मीटर (स्पष्ट ऊँचाई) से कम नहीं होगा:
- (य) ''कृषि उपयोग साधन'' से अभिप्राय है, ऐसा विकास तथा गतिविधियां, जो कृषि संबंधी कार्यों को करने में सहायक रूप में अपेक्षित है, जैसे नलकूप, पम्प, चैम्बर, वायु चक्की, सिंचाई, नाले, पक्के प्लेटफार्म, बाड़ लगाना तथा चारदीवारी बनाना, जल नलके आदि;
- (य क) "लघु उद्योग" से अभिप्राय है, ऐसी औद्योगिक इकाई जो उद्योग विभाग द्वारा लघु उद्योग के रूप में पंजीकृत हो;
- (य ख) ''कृषि आधारित उद्योग'' से अभिप्राय है, ऐसी औद्योगिक इकाई, जो खाद्यान्न, फलों या कृषि अपशिष्ट का उपयोग कच्चे माल के रूप में करती है;
- (य ग) ''सूचना प्रौद्योगिकी औद्योगिक इकाई'' से अभिप्राय है, हरियाणा सरकार की सूचना प्रौद्योगिकी नीति, 2000 के अनुबन्ध में तथा इस अधिसूचना के परिशिष्ट—1 में शामिल उद्योगों की श्रेणियां तथा/ अथवा जो हरियाणा सरकार द्वारा, समय—समय पर परिभाषित की जाये;
- (य घ) ''साईबर पार्क / सूचना प्रौद्योगिकी पार्क'' से अभिप्राय है, वह क्षेत्र जो केवल साफ्टवेयर विकास सम्बन्धी क्रिया कलापों का पता लगाने तथा सूचना प्रौद्योगिकी को समर्थ बनाने वाली सेवाओं के लिए विकसित हों, इसमें किसी भी प्रकार के विनिर्माण (असैम्बलिंग क्रियाकलापों सहित) की अनुमति प्रदान नहीं की जाएगी।
- (य ड) "साईबर सिटी" से अभिप्राय है, केन्द्रकीय सूचना/प्रौद्योगिकी परिकल्पना के लिए विकसित और कम्पनियों/ सूचना प्रौद्योगिकी आधारित सेवाओं के मध्यम तथा बड़े साफटवेयर उत्पन्न किए जाने के लिए अति उच्चतम गुणवत्ता का मूलभूत ढांचा, उत्तम परिस्थितियां और उच्च गति संचार से आत्मिनर्भर परिपूर्ण शहर, जहां विनिर्माण ईकाईयों को अनुमत नहीं किया जाएगा;
- (ल च) ''हरित पट्टी'' से अभिप्राय है, भूमि की वो पट्टियां जो विकास योजना में सेक्टर / परिधि सड़कों के साथ—साथ फैली हुई हैं, जो भविष्य में विनिर्दिष्ट सड़क को चौड़ा करने के लिए उपयोग हो; तथा
- (ल छ) किन्हीं अन्य अभिव्यक्तियों का वही अर्थ होगा, जो उन्हें पंजाब अनुसूचित सड़क तथा नियंत्रित क्षेत्र अनियमित विकास निर्बन्धन अधिनियम, 1963 (1963 का पंजाब अधिनियम 41) तथा हरियाणा नगरपालिका अधिनियम, 1973 (1973 का 24) तथा उसके अधीन बनाए गए नियमों में उन्हें दिया गया है।

III. मुख्य भूमि उपयोग/अंचल

- (1) (i) रिहायशी अंचल
 - (ii) वाणिज्यिक अंचल
 - (iii) औद्योगिक अंचल
 - (iv) परिवहन तथा संचार अंचल
 - (v) जन उपयोगिता अंचल
 - (vi) सार्वजनिक तथा अर्ध-सार्वजनिक अंचल
 - (vii) खुले स्थान अंचल
 - (viii) कृषि अंचल
 - (ix) प्राकृतिक संरक्षण क्षेत्र / आरक्षित पॉकेट
- (2) मुख्य भूमि उपयोगों का वर्गीकरण परिशिष्ट क के अनुसार है।

IV सेक्टरों में विभाजन:-

उपर्युक्त अंचल विनियमन—III में क्रम संख्या—(i) से (vii) पर वर्णित मुख्य भूमि उपयोग, जो भवन प्रयोजनार्थ भूमि उपयोग हैं, जिन्हें इन सेक्टरों की मुख्य सड़कों के आरक्षण हेतु दर्शाई गई हदबन्दी के अनुसार सेक्टरों में विभाजित किया गया है और प्रत्येक सेक्टर को ड्राईंग में दिखाये अनुसार एक निश्चित संख्या दी गई है।

V मुख्य उपयोगों में भूमि उपयोग :--

मुख्य, सहायक तथा गौण उपयोग जो इन विनियमों तथा नियमों को अन्य अपेक्षाओं के अध्यधीन हैं, को मुख्य भूमि उपयोग अंचल में अनुमति दी जा सकती है, उनकी सूची परिशिष्ट ख पर दी गई है जो इन विनियमों के साथ जोड़े गये है।

VI विकास के लिए अनुपयुक्त सेक्टर:-

विभिन्न सेक्टरों में भवन परियोजनार्थ, भूमि उपयोग के लिए आरक्षण होते हुए भी, निदेशक, नियंत्रित क्षेत्र के सघन तथा किफायती विकास के दृष्टिगत अपने भूमि उपयोग में किसी प्रकार के परिवर्तन के लिए अथवा उस पर किसी भवन के निर्माण के लिए ऐसे समय तक अनुमित नहीं देगा जब तक वह अपनी संतुष्टि सुनिश्चित नहीं कर लेता है कि इन सेक्टरों के लिए जल सप्लाई, जल मल निकास व्यवस्था तथा अन्य सुविधायें, उपलब्ध नहीं हो जाती हैं।

VII केवल सरकारी उपक्रमों के माध्यम से विकसित किये जाने वाले सेक्टर:-

सरकार अपने द्वारा या उसकी एजेंसियों द्वारा, विकास के लिए कोई सेक्टर अधिसूचित कर सकती हैं, ऐसे मामले में ऐसे सेक्टरों में भूमि उपयोग के परिवर्तन या अनुज्ञप्ति प्रदान करने के लिए आगे कोई भी अनुमति अनुमत नहीं की जाएगी।

VIII मुख्य सड़कों के लिए भूमि आरक्षण:-

(1) ड्राईंग में चिहिनत की गई मुख्य सड़कों के लिए भूमि का आरक्षण निम्नानुसार किया जायेगाः

क्रम	वर्गीकरण	सड़क का नाम	भूमि आरक्षण	
न्नग्रा संख्या	41147(-1	राञ्चर यहा सारा	ત્રુપ બાલાન	
1.	वी—1	बाईपास	दोनों तरफ 100 मीटर चौडी हरित पट्टी	
			सहित 75 मीटर चौड़ी सड़क।	
2.	वी—1ए	रोहतक–दिल्ली राष्ट्रीय राजमार्ग संख्या	दोनों ओर 60 मीटर चौड़ी हरित पट्टी सहित	
		9	वर्तमान चौड़ाई।	
3.	वी — 2	सेक्टर विभाजक सड़क	60 मीटर चौड़ी सड़क।	
4.	वी—2ए	परिधीय सड़क	दोनों ओर 30 मीटर चौड़ी हरित पट्टी सहित	
			60 मीटर चौड़ाई।	
5.	वी—2बी	परिधीय सड़क	बाहरी ओर 30 मीटर चौड़ी हरित पट्टी सहित	
			60 मीटर चौड़ाई।	
6.	वी—2सी	बहादुरगढ़–झज्जर, बहादुरगढ़–बेरी,	दोनो ओर 30 मीटर चौड़ी हरित पट्टी सहित	
		बहादुरगढ़– सिद्धीपुर,	60 मीटर चौड़ाई।	
		बहादुरगढ़–बादली सड़क		
7.	वी—3	सेक्टर विभाजक सड़क	45 मीटर चौड़ी सड़क।	
8.	वी—3ए	बहादुरगढ़–नजफगढ़,	वर्तमान चौड़ाई को 45 मीटर चौड़ा किया	
		बहादुरगढ़–नाहरा सड़क	जाना है।	
9.	वी-3बी	सेक्टर विभाजक सड़क	30 मीटर चौड़ी सड़क (विकसित सड़क)	

- (2) अन्य सड़कों की चौड़ाई और सीधाई, सेक्टर प्लान के अनुसार अथवा कालोनियों की अनुमोदित अभिविन्यास योजना के अनुसार होगी।
- (3) हरियाणा शहरी विकास प्राधिकरण तथा गैर—सरकारी उपनिवेशकों द्वारा विकसित किए जाने वाले सेक्टर/कालोनी के लिए तैयार योजनाओं को अनुमोदित करते समय मुख्य सड़कों तथा निकटवर्ती हरित पट्टी, यदि कोई हो, के अधीन आने वाले क्षेत्र को केवल 50 प्रतिशत का लाभ प्लाटिड/वर्ग आवास कालोनी के प्लाटएबल/फर्श क्षेत्र अनुपात के लिए किया जाएगा। लेकिन सेक्टर योजना में शुद्ध योजनागत क्षेत्र में शामिल सड़कों की स्थिति में पूर्ण फर्श क्षेत्र अनुपात का लाभ दिया जायेगा। वाणिज्यिक कालोनी तथा सूचना प्रौद्योगिकी पार्क/साईबर सिटी की दशा में कुल क्षेत्र के 10 प्रतिशत के फर्श क्षेत्र अनुपात का लाभ या हरित पट्टी तथा सैक्टर सड़क में आने वाले क्षेत्र, इसमें से जो भी कम हो, दिया जाएगा।
- (4) व्यापार योग्य फर्श क्षेत्र अनुपात का लाभ, विनिर्दिष्ट पॉलिसी के अनुसार सेक्टर सड़क या हरित पट्टी तथा खुला क्षेत्र अंचलों के अधीन आने वाली भूमि के लिए प्रदान की गई अनुज्ञप्तियों के लिए अनुज्ञात किया जा सकता।

IX वर्तमान या भूमि उपयोग में वैध परिवर्तन की अनुमति प्राप्त अननुरूप उपयोग:-

- (1) विकास योजना में अननुरूप उपयोग अंचल से भिन्न अंचलों में अवस्थित स्थित विद्यमान परियोजना के संबंध में, निदेशक द्वारा निर्धारित की जाने वाली नियत अविध के लिए विकास योजना में प्रकाशन की तिथि से दस वर्ष की अनिधक अविध से औद्योगिक अननुरूप उपयोग जारी रखने की अनुमित दी जाएगी बशर्ते कि सम्बद्ध भवन का स्वामी:—
 - (क) निदेशक को स्थल के बाह्य विकास के लिए, उस द्वारा यथानिर्धारित अनुपातिक प्रभारों को तथा जब भी निदेशक द्वारा इस निमित्त ऐसा करने के लिए कहा जाये, के भुगतान का वचन देता है;
 - (ख) अंतरिम अवधि के दौरान निदेशक की संतुष्टि के अनुसार बहिस्राव के निष्कासन की सुनिश्चित व्यवस्था करें:
 - (ग) अनन्रूप उपयोग के क्षेत्र में विद्यमान परियोजना के विस्तार की अनुमित नहीं होगी ।
- (2) उन परियोजनाओं के बारे में, जिन्हें भूमि उपयोग की मान्य स्वीकृति है तथा जो विकास योजना में अनुरूप उपयोग अंचल से भिन्न अवस्थित है, ऐसे अननुरूप उपयोग चलते रहने के लिए अनुमत किए जाएंगे, बशर्ते कि सम्बद्ध भवन का स्वामी :-
 - (क) निदेशक को स्थल के बाह्य विकास के लिए उस द्वारा यथा निर्धारित अनुपातिक प्रभारों तथा जब निदेशक द्वारा इस निमित्त ऐसा करने के लिए कहा जाये के भुगतान का वचन देता है;
 - (ख) अंतरिम अवधि के दौरान निदेशक की संतुष्टि के अनुसार बहिस्राव के लिए संतोषजनक व्यवस्था करें।

X अननुरूप उपयोग बन्द करनाः-

- (1) यदि किसी भूमि का अननुरूप उपयोग दो वर्ष या इससे अधिक अवधि के लिए लगातार बन्द रहा हो, तो यह समाप्त हुआ समझा जायेगा और केवल अनुरूप अनुमत उपयोग के अनुसार ही भूमि के पुनःउपयोग या पुनःविकास की अनुमति दी जायेगी।
- (2) यदि अनुरूप उपयोग भवन, आग, बाढ़, विस्फोट, भूकम्प, लड़ाई, दंगा या किसी अन्य प्राकृतिक आपदा से इसके पुनरूत्पादन मूल्य के पचास प्रतिशत या इससे अधिक क्षतिग्रस्त हो जाता है, तो उसे केवल अनुमत उपयोग के लिए पुनःविकसित करने की अनुमति दी जायेगी।
- (3) खण्ड IX के अधीन भामिल परियोजनाओं के समाप्त होने के बाद, भूमि केवल अनुरूप उपयोग के लिए पुनः विकसित करने या उपयोग में लाने के लिए अनुमति की जायेगी।
- (4) खण्ड IX (1) के अधीन नियत अविध की समाप्ति के बाद भूमि केवल अनुरूप उपयोग के लिए पुनः विकसित या उपयोग में लाने के लिए अनुमत की जाएगी।

XI सेक्टर योजना और आंचलिक योजना के अनुरूप विकास:-

विनियम IX में यथा उपबन्धित को छोड़कर, मुख्य भूमि उपयोग किसी भी जिसमें भूमि को भवन निर्माण प्रयोजनार्थ उपयोग के लिए तब तक अनुमत नहीं किया जाएगा जब तक कि प्रस्तावित उपयोग और विकास, सेक्टर योजना और आंचलिक योजना अथवा अनुमोदित कालोनी योजना, जिससे भूमि अवस्थित है, में दिखाये गये ब्यौरे के अनुसार न हो।

XII अनुमोदित अभिविन्यास या आंचलिक योजना का भाग बनने वाले विशिष्टि स्थल:-

किसी प्लाट पर भवन निर्माण या पुनःनिर्माण की अनुमति तब तक नहीं दी जायेगी जब तक कि-

- (i) प्लाट अनुमोदित कालोनी का भाग न हो या प्लाट ऐसे क्षेत्र में न हो, जिसके लिए विनियम XVII में यथा उपबन्धित अनुसार छूट दी गई है; तथा
- (ii) निदेशक की संतुष्टि अनुसार प्लाट तक पहुंच के लिए सड़क की व्यवस्था न हो और सड़क न बनी हो।

 XIII विभिन्न प्रकार के भवनों के प्लाटों का न्यूनतम आकार:—
 - (1) विभिन्न प्रकार के उपयोगों के लिए प्लाटों के न्यूनतम आकार निम्न अनुसार होंगे:--

क्रम	भूमि उपयोग	आकार
संख्या		
(i)	रिहायशी प्लाट	50 वर्ग मीटर
(ii)	सरकार द्वारा अनुमोदित आर्थिक सहायता प्राप्त औद्योगिक आवास या गन्दी बस्तियों में रहने वालों के लिए आवास स्कीम में रिहायशी प्लाट	35 वर्ग मीटर
(iii)	दुकान एवं रिहायशी प्लाट	100 वर्ग मीटर
(iv)	शापिंग बूथ जिनमें सामने बरामदा या पत्थर तथा ईंट का पैदल मार्ग शामिल हो	20 वर्ग मीटर
(v)	स्थानीय सेवा उद्योग प्लाट	100 वर्ग मीटर
(vi)	हल्के उद्योग प्लाट	250 वर्ग मीटर
(vii)	मध्यम उद्योग प्लाट	8000 वर्ग मीटर

(2) रिहायशी और वाणिज्य विकास के लिये वर्ग आवास कालोनी, प्लाटिड रिहायशी कालोनी और वाणिज्य कालोनी के लिए क्षेत्र मानदण्ड समय—समय पर अधिसूचित पॉलिसियों के अनुसार होंगे। तथापि, यदि वर्ग आवास स्कीम हिरयाणा शहरी विकास प्राधिकरण या किसी अन्य सरकारी एजेंसी द्वारा प्रारम्भ की जाती है, तो वर्ग आवास स्थल का आकार योजना में यथा विनिर्दिष्ट होगा।

XIV विभिन्न प्रकार के भवनों के अधीन आच्छादित क्षेत्र, ऊँचाई और आकार:-

विशिष्ट प्लॉट/स्थल के लिए पर अनुमत आच्छादित क्षेत्र, फर्श क्षेत्र अनुपात तथा ऊँचाई पैरामीटरों, भवन संहिता/ नियमों तथा/या ऐसे प्लाट/स्थल के जोनिंग प्लान में यथा अधिकथित विहित पॉलिसी द्वारा शासित होगी।

$\mathbf{X}\mathbf{V}$ भवनों की अगली ओर तथा पिछली ओर भवन पंक्ति:-

ये भवन संहिता/नियमों के अनुसार तथा/या ऐसे क्षेत्र के जोनिंग प्लान में यथा अधिकथित उपबन्धित होगी। XVI वास्तकला संबंधी नियंत्रण:—

जहां कहीं भी वास्तुकला संबंधी नियंत्रण आवश्यक समझा जाता है, तो प्रत्येक भवन, हरियाणा भवन संहिता, 2017 के खण्ड 6.4 के अधीन बनाये गए वास्तुकला संबंधी नियंत्रण के अनुरूप होगा।

XVII कृषि अंचल में भूमि उपयोग में ढील:-

कृषि अंचल में आने वाली किसी भूमि के मामले में, सरकार इस विकास योजना के उपबन्धों में निम्नलिखित हेतु ढील दे सकती है.–

- (क) भूमि के आवासीय अथवा औद्योगिक कालोनी में उपयोग तथा विकास हेतु, बशर्ते उपनिवेशक द्वारा यह भूमि वास्तविक तिथि से पहले उक्त उपयोग तथा विकास के लिए क्य की गई हो और उपनिवेशक नियमानुसार इस प्रयोजन के लिए अनुमति प्राप्त करता है।
- (ख) व्यक्तिगत स्थल के रूप में भूमि उपयोग हेत् (औद्योगिक कालोनी से भिन्न) बशर्तें कि:-
 - (i) वास्तविक तिथि से पूर्व भूमि कय की गई हो;
 - (ii) सरकार की संतुष्टि हो गई है कि उद्योग की आवश्यकता इस प्रकार की है कि उपयुक्त अंचल में वैकल्पिक स्थल के नियतन की प्रतीक्षा नहीं की जा सकती;
 - (iii) भू-स्वामी, नियमों के यथा अपेक्षित अधीन भवन निर्माण के लिए अनुमति प्राप्त करता है; तथा
 - (iv) भू—स्वामी, निदेशक द्वारा निर्धारित अनुपातिक प्रभारों जब भी कभी इस निमित्त निदेशक द्वारा मांग की जाये, का भुगतान निदेशक को करने का वचन देता है और अंतरिम अवधि में बहिस्राव के निकास की संतोषजनक व्यवस्था करता है।

व्याख्या:— इस विनियम में प्रयुक्त शब्द "क्रय" से अभिप्राय है, विभिन्न प्रयोजनों इत्यादि हेतु ऐसी अवधि, जो सरकार, द्वारा विनिर्दिष्ट की जाए, के लिए पूर्ण स्वामित्व अधिकारों / पट्टा अधिकारों का अर्जन।

XVIII सघनताः-

दोनों ओर से 20 प्रतिशत की विभिन्नता सिंहत प्रत्येक रिहायशी सेक्टर ड्राईंग में दर्शायी गई सेक्टर सघनता तथा इसके अतिरिक्त नई एकीकृत अनुज्ञापन पॉलिसी, दीन दयाल जन आवास योजना पॉलिसी तथा अफोर्डऐबल ग्रुप हाऊसिंग पॉलिसी, में यथा विहित सघनता में विकसित किया जाएगा। 20 प्रतिशत ग्रुप हाऊसिंग कम्पोनेन्ट पॉलिसी रिहायशी सेक्टर में भी लागू होगी।

XIX कृषि अंचल में आबादी देह के बाहर फार्म गृहों की व्यवस्था:--

केवल भू—स्वामी (स्वामियों) को वास्तविक उपयोग के लिए फार्म गृहों की अनुमित दी जाएगी बशर्तें किसी शहरी क्षेत्र में उसका अपना कोई आवास नहीं हो, चूंकि कृषि अंचल में फार्म गृहों को अनुमत करने के लिए वास्तविक उद्देश्य फार्म के छोटे भाग पर कृषकों की आवासीय आवश्यकताओं को पूरा करना है तािक वह उस फार्म पर निवास करने के दौरान अपने कृषि उत्पाद की देख—रेख कर सकें। इसलिए आबादी देह के बाहर कृषि अंचल में निम्नलिखित शर्तों पर फार्म गृह अनुमत किया जा सकता है, यदि भूमि का क्षेत्र 2 एकड़ या इससे अधिक है:—

	फार्म हाउस का आकार	आवासीय इकाई का मुख्य	मुख्य आवासीय इकाई का
		भवन	अनुषंगी भवन
(i) स्थल	न्यूनतम २ एकड़ तक परन्तु विकास	250 वर्ग गज के समकक्ष	फार्म की भूमि का एक
आच्छादन	प्लैन अनुसार सड़क आरक्षण तथा	रिहायशी प्लाट के लिये	
	प्रस्तावित सड़क की चौड़ाई के	यथा लागू।	क्वार्टरों के लिए 40 प्रतिशत
	अर्न्तगत आने वाली भूमि/क्षेत्र भूमि		से अधिक का उपयोग नहीं
	उपयोग में परिवर्तन की अनुमति हेतु		किया जायेगा)
	मान्य नहीं होगी। किन्तु कृषि अंचल मे		
	आने वाले आवेदित 2 एकड़ क्षेत्र में से		
	हरित पट्टी/ प्रतिबंधित पट्टी के		
	अर्न्तगत आने वाले क्षेत्र को छोड़ते हुए		
	शेष क्षेत्र 1.5 एकड़ से कम नहीं होना		
	चाहिए।		

फार्म हाउस का आकार	आवासीय इकाई का मुख्य भवन	मुख्य आवासीय इकाई का अनुषंगी भवन
3 एकड़ तक	375 वर्ग गज के समकक्ष रिहायशी प्लाट के लिये यथा लागू।	— सम —
4 एकड़ तक और अधिक	500 वर्ग गज के समकक्ष रिहायशी प्लाट के लिये यथा लागू।	—सम—
(ii) ऊंचाई तथा मंजिल	11 मीटर, तीन मंजिलें	4 मीटर, एकल मंजिल

(iii) दूरी: कृषि भूमि के सभी किनारों से कम से कम 10 मीटर दूर बशर्तें कि यदि फार्म हाऊस से संबद्ध भूमि सड़क के साथ लगती है तो गृह का निर्माण सड़क के किनारे से कम से कम निम्नलिखित दूरी पर किया जायेगा:—

क्रम संख्या	सड़क	न्यूनतम दूरी
(ক)	जहां सड़क अनुसूचित सड़क का बाईपास है	100 मीटर
(ख)	जहां सड़क अनुसूचित सड़क है	30 मीटर अथवा जैसा कि विकास योजना में दर्शाया गया है।
(ग)	कोई अन्य सड़क	10 मीटर

(iv) पहुँच सड़क:-

राजस्व रिकार्ड में परिभाषित कोई राजस्व रास्ता/सड़क।

(v) तहखाना :- तहखाने को भू-तल आच्छादन की अधिकतम सीमा तक अनुमत किया जाएगा और उपयोगों को हिरयाणा भवन संहिता, 2017 के अनुसार अनुमित दी जाएगी।

(vi) पुश्तवान, अटारी तथा परछती तल:-

पुश्तवान, अटारी और परछती तल की अनुमित भवन के भीतर उक्त निर्बन्धनों के साथ—साथ विकास योजना के अंचल विनियमों के खण्ड—II में दी गई परिभाषा में नियत निर्बन्धनों के अध्यधीन दी जायेगी।

(vii) सेवायें, जल आपूर्ति तथा जल निकास:-

- (क) यदि फार्म गृह का निर्माण किया जाता है, तो फार्म में मानव उपयोग के लिए अच्छी पीने योग्य जल आपूर्ति उपलब्ध होनी चाहिए।
- (ख) डेरी फार्म के मामले में छायावानों की सफाई हेतु खुली स्वच्छ निकास नालियां अथवा ढकी हुई निकास नालियों की व्यवस्था की जाये, सभी भवनों के मामले में, वर्षा के पानी के निकास हेतु निकास नालियों की व्यवस्था की जानी है।
- (ग) नियमों के उपबन्धों के अनुसार मानव और पशुओं के अपशिष्ट निस्तारण के लिए मलाश्य की व्यवस्था की जाये।
- (घ) मलाश्य और खुले कुएं अथवा नलकुप के बीच दुरी नियमों में यथा उपबन्धित अनुसार होगी ;
- (viii) स्वामी को फार्म हाऊस की मुख्य आवासीय इकाई और उसके अनुषंगी भाग के इर्द–गिर्द चार दीवारी के निर्माण की अनुमति दी जायेगी तथा फार्म के शेष क्षेत्र के इर्द–गिर्द कंटीली तारों वाली बाड़ लगाने की अनुमति होगी।
- (ix) केन्द्रीय भूजल बोर्ड द्वारा यथा अपेक्षित अत्यधिक शोषित अथवा संकटमय क्षेत्र से भिन्न क्षेत्र में फार्म हाऊस की स्थापना हेतु भूमि उपयोग में परिवर्तन की अनुमित पर विचार किया जायेगाः

परन्तु सरकार ग्रामीण अंचल की उचित उपयोगिता के लिए राज्य सरकार/राज्य अभिकरण द्वारा प्रायोजित किसी स्कीम के लिए फार्म के न्यूनतम आकार में संशोधन कर सकती है।

XX सूचना प्रौद्योगिकी इकाईयों और साईबर पार्क / साईबर शहरों के लिए उपबन्ध:-

(i) अवस्थिति:-

- (क) सूचना प्रौद्योगिकी इकाईयां केवल औद्योगिक क्षेत्र / औद्योगिक अंचल में अवस्थित होंगी;
- (ख) साईबर पार्क / सूचना प्रौद्योगिकी पार्क एकीकृत विकास के रूप में सेक्टर सड़क के साथ लगते हुए या तो औद्योगिक क्षेत्र या औद्योगिक अंचल में अवस्थित होंगे। यद्यपि, ऐसे पार्कों में किन्हीं विनिर्माण इकाईयों को अनुज्ञात नहीं किया जाएगा।
- (ग) साईबर शहर:- ऐसी सुविधा की अवस्थिति सरकार द्वारा विनिश्चित की जाएगी।

(ii) आकार:--

क्रम संख्या	प्रकार	आकार
1	सूचना प्रौद्यागिकी औद्योगिक इकाई	1 से 5 एकड़
2	साईबर पार्क / सूचना प्रौद्योगिकी पार्क	5 से 15 एकड़
3	साईबर सिटी	न्यूनतम ५० एकड़

(iii) विविध:-

(I) पार्किंग:-

पार्किंग, समय समय पर यथा संशोधित, हरियाणा भवन संहिता, 2017 के उपबन्धों के अनुसार होगी।

(II) अन्य क्रियाकलाप:-

- (क) आनुषांगिक वाणिज्यिक क्रियाकलाप जैसे बैंक रैस्टोरैन्ट, इंश्योरैंस कार्यालय इत्यादि, को साईबर पार्क / सूचना प्रौद्योगिकी पार्क के कुल क्षेत्र के 4 प्रतिशत के निर्बन्धन के अधीन रहते हुए अनुमति दी जायेगी;
- (ख) साईबर शहर के क्षेत्र का केवल 5 प्रतिशत क्षेत्र वर्ग आवास के लिए अनुमत किया जायेगा तथा इस साईबर शहर का कुल क्षेत्र 4 प्रतिशत के वाणिज्यिक/संस्थागत उपयोगों के लिए अनुमत किया जायेगा:
- (ग) साईबर शहर में रिहायशी प्लाटिड विकास की अनुमित नहीं दी जायेगी;
- (घ) साईबर शहर परियोजना यदि कृषि अंचल में अनुज्ञप्त हो तो, उद्यमी जल आपूर्ति तथा अन्य सुविधाओं जैसे मल जलनिस्तारण/निकास नालियां इत्यादि का प्रबन्ध करेगा।
- (III) सरकार, कोई अन्य शर्त अधिरोपित कर सकती है, जैसा समय–समय पर आवश्यक समझे।

XXI संचार टावरों की स्थापना :-

नियन्त्रित क्षेत्र के भीतर मोबाइल टावरों की अनुमित, समय—समय पर यथा संशोधित, विभाग के मैमो दिनांक 10 मार्च, 2015 की नीति/अनुदेशों के अनुसार प्रदान की जाएगी।

XXII भूकंम्पीय आपदा से सुरक्षा :-

भारतीय मानक आई.एस. 1893:2002 के भूकम्पीय क्षेत्र मानचित्र के अनुसार विकास योजना का क्षेत्र भूकम्पीय क्षेत्र जोन IV अंतर्गत आता है तथा इसे उच्च जोखिम क्षेत्र माना गया है। उपरोक्त को ध्यान में रखते हुए, सम्पूर्ण शहरी विकास घटना तीव्रता VIII' की सम्भाव्यता हेतु सुरक्षा की जांच की जाएगी तथा भवनों तथा अवसंरचना में अपेक्षित भूकम्पीय प्रतिरोध, जो आवश्यक पाया जाए, उन्नत किया जाएगा।

XXIII नियंत्रित क्षेत्र में स्थित ईंटों के भट्टे :-

नियंत्रित क्षेत्रों में स्थित ईंट भट्टे सक्षम प्राधिकारी द्वारा, समय–समय पर जारी, संबंधित नीति/दिशा–निर्देशों के द्वारा शासित होंगे।

XXIV विकास योजना में ढील :-

सरकार अत्यन्त किंदिनाई की दशा में अथवा वास्तविक तिथि से पूर्व निर्मित किसी ढांचे को बचाने की दृष्टि से विकास प्रभारों के भुगतान पर और ऐसी अन्य शर्तों पर, जो वह लगाना उचित समझे, साम्य और न्याय के सिद्धान्तों पर विकास योजना के किन्हीं उपबन्धों में ढील दे सकती है।

परिशिष्ट क भूमि उपयोगों का वर्गीकरण

मुख्य कोड	उपकोड	मुख्य वर्ग	उपवर्ग
100		रिहायशी	पड़ोस–पद्धति पर रिहायशी सेक्टर
200		वाणिज्यिक	
	210		परचून व्यवसाय
	220		थोक व्यवसाय
	230		भांडागार और भंडारण
	240		कार्यालय और बैंक जिसमें सरकारी कार्यालय भी शामिल है।

मुख्य कोड	उपकोड	मुख्य वर्ग	उपवर्ग
	250		रैस्तरां, होटल तथा अस्थाई बोर्डिंग हाऊस, जिनमें धर्मशाला, पर्यटक गृह आदि जैसे रिहायशी आवास की व्यवस्था वाली सार्वजनिक सहायता संस्थायें भी
			शामिल हैं
	260		वाणिज्यिक आधार पर सिनेमा तथा लोगों के एकत्रित होने वाले अन्य स्थान
	270		व्यवसायिक स्थापनायं
300		औद्योगिक	
	310		सेवा उद्योग
	320		हल्के उद्योग
	330		व्यापक उद्योग
400		परिवहन तथा संग	चार
	420		सड़कें, सड़क परिवहन डिपो और पार्किंग क्षेत्र, ईंधन स्टेशन तथा गैरज
	450		दूरभाष केन्द्र आदि
	460		प्रसारण केन्द्र
	470		दूरदर्शन केन्द्र
500		जन उपयोगितायें	
	510		जल आपूर्ति संस्थापन जिसमें शोधन संयंत्र भी शामिल है
	520		जल निकास और सफाई संस्थापनायें जिनमें निस्तारण कार्य भी शामिल है,
	530		विद्युत भावित संयंत्र उपस्टेशन आदि
	540		गैस संस्थापन और गैस कार्य
	550		टोस अपशिष्ट प्रबन्धन स्थल
600		सरकारी और अर्धसरकारी	
	610		सरकारी प्रशासन, केन्द्रीय सचिवालय, जिला कार्यालय, विधि न्यायालय, जेलें, पुलिस थाने, राज्यपाल तथा राष्ट्रपति निवास
	620		शिक्षा, सांस्कृतिक और धार्मिक संस्थायें
	630		चिकित्सा तथा स्वास्थ्य संस्थायें
	640		मुख्यतः गैर वाणिज्यिक किस्म के थियेटर आपेरा हाऊस आदि जैसी सांस्कृतिक संस्थायें
700		खुले स्थान	
	710		खेलकूद मैदान, स्टेडियम, क्रीड़ा मैदान
	720		पार्क
	730		हरित पट्टी, बाग तथा अन्य मनोरंजन संबंधी उपयोग
	740		कब्रिस्तान, शमशान घाट आदि
	750		ईंधन स्टेशन तथा बस पंक्ति शैल्टर
	760		जल निकाय / झील
800		कृषि भूमि	
	810		मार्किट गार्डन
	820		फलोद्यान तथा नर्सरियां
	830		प्रधान फसल के अन्तर्गत भूमि
	840		चराई भूमि तथा चरागाहें
	850		वन भूमि

मुख्य कोड	उपकोड	मुख्य वर्ग	उपवर्ग
	860		दलदल
	870		बंजर भूमि
	880		जलमग्न भूमि
	890		डेरी फार्मिंग
1000		प्राकृतिक संरक्षण	कृषि तथा बागवानी
		जोन / आरक्षित	मत्स्य पालन
		पॉकेट/अनिर्धारित	वन रोपण सहित सामाजिक वानिकी / पौधारोपण
		पॉकेट	सक्षम प्राधिकारी की अनुमति से क्षेत्र के 0.5 प्रतिशत
			से अनधिक निर्माण सहित क्षेत्रीय मनोरंजन
			गतिविधियां

परिशिष्ट ख

मुख्य भूमि उपयोगों के अधीन दी गई अनुमत गतिविधियां, सरकार द्वारा स्वीकृत पालिसी/मापदंडों तथा सेक्टर/कालोनी/स्कीम योजना में सक्षम प्राधिकारी द्वारा स्थल पर यथा अनुमत अनुसार अनुमत की जाएगी।

I. रिहायशी जोन

- (i) आवासीय
- (ii) सामाजिक, सामुदायिक, धार्मिक और आमोद प्रमोद गृह
- (iii) जन उपयोगिता भवन
- (iv) शैक्षणिक भवन और सभी प्रकार के विद्यालय और महाविद्यालय, जहाँ आवश्यक हो
- (v) स्वास्थ्य संस्थायें
- (vi) सिनेमा
- (vii) वाणिज्यिक और व्यवसायिक कार्यालय
- (viii) परचून की दुकानें, ढाबे और रैस्तरां
- (ix) स्थानीय सेवा उद्योग
- (x) ईंधन स्टेशन
- (xi) बस स्टाप, तांगा, टैक्सी, स्कूटर तथा आटो/रिक्शा स्टैंड
- (xii) नर्सरियां और हरित गृह
- (xiii) रिहायशी उपयोग में अनुषंगी कोई अन्य छोटी-छोटी जरूरतें
- (xiv) सितारा होटल
- (xv) क्लब / सामुदायिक केन्द्र
- (xvi) संचार टावर
- (xvii) अतिथि/बोर्डिंग आवास
- (xviii) कोई अन्य उपयोग, जिसे सरकार लोकहित में विनिश्चित करे।

II. वाणिज्यिक जोन

- (i) परचून व्यापार
- (ii) थोक व्यापार
- (iii) भांडागार और भंडारण
- (iv) वाणिज्यिक कार्यालय और बैंक
- (v) रैस्तरां तथा अस्थाई आवास गृह जिसमें धर्मशाला और पर्यटक गृह आदि जैसे रिहायशी स्थान प्रदान करने वाले सार्वजनिक सहायता संस्थाएं शामिल हैं
- (vi) सिनेमा, होटल, मोटल तथा वाणिज्यिक आधार पर चलने वाले और लोगों के इकट्ठा होने वाले स्थान जैसे थियेटर, क्लब, ड्रामा क्लब आदि
- (vii) व्यवसायिक स्थापनायें
- (viii) प्रथम तथा उच्चतर मंजिलों पर निवास
- (ix) स्थानीय सेवा उद्योग
- (x) जन उपयोगिता भवन

- (xi) ईंधन स्टेशन और सर्विस गैरेज
- (xii) माल चढ़ाने और उतारने वाले यार्ड
- (xiii) पार्किंग स्थल, बस स्टाप, टैक्सी, तांगा, आटो / रिक्शा स्टैंड
- (xiv) नगर पार्क
- (xv) संचार टावर
- (xvi) कोई अन्य उपयोग, जिसे सरकार लोकहित में विनिश्चित करे।

III. औद्योगिक अंचल

- (i) हल्के उद्योग
- (ii) मध्यम उद्योग
- (iii) घृणाजनक और परिसंकटमय उद्योग
- (iv) भारी उद्योग
- (v) सर्विस उद्योग
- (vi) भांडागार और भंडारण
- (vii) पार्किंग, माल चढाने और उतारने वाले क्षेत्र
- (viii) ट्रक स्टैंड/बस स्टाप, टैक्सी तांगा और आटो/रिक्शा स्टैंड
- (ix) सैक्टर के कुल क्षेत्रफल के तीन प्रतिशत की अधिकतम सीमा के अध्यधीन, जन-उपयोगिता, सामुदायिक भवन, परचून की दुकानें, बैंक, ढाबा, रैस्टोरैन्ट, दो/तीन/पांच सितारा होटल तथा बीमा कार्यालय निम्नानसार:—

क्रम	सुविधाओं	क्षे	त्र	क्षेत्र में	वाणिज्यिक	अधिकतम	फर्श क्षेत्र	पहुँच मार्ग
संख्या	का नाम	न्यूनत म	अधिक तम	सुविधाअ ों की संख्या	घटक	भूतल अच्छादन	अनुपात	
1.	ढाबा	500 वर्ग मीटर	1000 वर्ग मीटर	2	50वर्ग मीटर	४० प्रतिशत	0.40	न्यूनतम 18 मीटर
2.	रेस्टोरेंट	1000 वर्ग मीटर	2000 वर्ग मीटर	2	10 प्रतिशत	30 प्रतिशत	1.50	न्यूनतम 18 मीटर
3.	दो / तीन सितारा होटल	1.0 एकड़	2.5 एकड़	2	15 प्रतिशत	30 प्रतिशत	वाणिज्यिक पॉलिसी के अनुसार	न्यूनतम 24 मीटर
4.	पाँच सितारा होटल	2.5 एकड़	4.0 एकड़	1	15 प्रतिशत	30 प्रतिशत	वाणिज्यिक पॉलिसी के अनुसार	सर्विस सड़क के प्रावधान के साथ सेक्टर विभाजक सड़क

- (x) ईंधन स्टेशन तथा सर्विस गैरेज
- (xi) निदेशक द्वारा अनुमत लिक्वीड पैट्रोलियम गैस गोदाम
- (xii) साईबर पार्क / सूचना प्रौद्योगिकी पार्क / सूचना प्रौद्योगिकी औद्योगिक इकाइयां
- (xiii) स्वास्थ्य सविधाएं जैसे अस्पताल, डिस्पेंसरी, नर्सिंग होम तथा क्लीनिकः

क्रम	रुविधाओं का		क्षेत्र	क्षेत्र में	रिहायशी	अधिकतम	फर्श क्षेत्र
संख्या	नाम	न्यूनतम	अधिकतम	सुविधाओं की संख्या	घटक	भूतल आच्छादन	अनुपात
1.	अस्पताल	2.5 एकड़	5.0 एकड़	1	15 प्रतिशत	३३ प्रतिशत	100 प्रतिशत
2.	डिस्पेंसरी	1.0 एकड़	1.5 एकड़	1	15 प्रतिशत	33 प्रतिशत	100 प्रतिशत
3.	नर्सिंग होम	250 वर्ग मीटर	500 वर्ग मीटर	2	शून्य	60 प्रतिशत	100 प्रतिशत
4.	क्लीनिक	250 वर्ग मीटर	500 वर्ग मीटर	2	शून्य	60 प्रतिशत	100 प्रतिशत

- (xiv) औद्योगिक कालोनी कम से कम 15 एकड़ में होगी। इस क्षेत्र का उपयोग अपर मुख्य सचिव, नगर तथा ग्राम आयोजना विभाग हरियाणा द्वारा जारी यथा अद्यतन संशोधित पालिसी संख्या मिसलिनियस 388/पी.ए.(आर बी)/2015/7/16/2006—2टीसीपी, दिनांक प्रथम अक्तूबर, 2015 के अनुसार होगा।
- (xv) संचार टावर
- (xvi) तैयार मिश्रण कंकीट संयत्र, वेट मिश्रण संयत्र, गर्म मिश्रण संयत्र इत्यादि
- (xvii) धर्म कांटा
- (xviii) सर्विस गैरज, बिक्री / प्रदर्शन केन्द्र-एवं-सर्विस गैरज का विवरण निम्न प्रकार है

क्रम	सुविधा का	क्षेत्र (एक	ड़)	वाणिज्यिक	अधिकतम	দূর্ঘ	पहुंच मार्ग
संख्या	नाम	न्यूनतम	अधिकतम	घटक	भूतल	क्षेत्र	
		.,			आच्छादन	अनुपात	
1	सर्विस गैरज	0.5	1	शून्य	60 प्रतिशत	1.25	18 मीटर या सेक्टर सड़क के साथ प्रस्तावित सर्विस सड़क
2	बिक्री / प्रदर्शन केन्द्र—एवं— सर्विस गैरज	0.5	2	अनुज्ञेय फर्श क्षेत्र अनुपात का 10 प्रतिशत	60 प्रतिशत	1.25	18 मीटर या सेक्टर सड़क के साथ प्रस्तावित सर्विस सड़क

टिप्पणः — * वाणिज्यिक घटक के विषय में फीस तथा प्रभार वाणिज्यिक दरों पर उद्गृहीत किए जाएंगे;

- * विद्यमान / पहले से भूमि उपयोग परिवर्तन अनुमित प्राप्त सर्विस गैराज को बिकी / प्रदर्शन केन्द्र की अनुमित देने हेतु उपरोक्त मानदण्डों को पूर्ण करने की दशा में ही विचार किया जाएगा।
- (xix) कोई अन्य उपयोग, जिसे सरकार लोकहित में विनिश्चित करे।

IV. परिवहन तथा संचार अंचल

- (i) रेलवे यार्ड, रेलवे स्टेशन और साईडिंग
- (ii) परिवहन नगर, सडकें और परिवहन डिपो और पार्किंग क्षेत्र
- (iii) हवाई अडडा और हवाई स्टेशन
- (iv) दूरभाष केन्द्र
- (v) प्रसारण केन्द्र
- (vi) दूरदर्शन केन्द्र
- (vii) अनुमोदित स्थलों और स्थानों पर कृषि, बागवानी और नर्सरिज
- (viii) ईंधन स्टेशन और सर्विस गैरेज
- (ix) पार्किंग स्थल, बस स्टाप-शैल्टर, टैक्सी, टांगा और ओटो / रिक्शा स्टैंड
- (x) रसद केन्द्रों / कंटेनर यार्डस, अंर्तदेशीय कंटेनर डिपो, कंटेनर फेट स्टेशन
- (xi) संचार टावर
- (xii) धर्म कांटा
- (xiii) सेक्टर के कुल क्षेत्र की 20 प्रतिशत की अधिकतम सीमा तक भांडागार
- (xiv) मौजूदा नीति के अनुसार ढाबा।

V. जन उपयोगितायें

- (i) जल सप्लाई, संस्थापनाएं इसमें शोधन संयंत्र भी शामिल हैं
- (ii) जल निकास और सफाई स्थापनाएं इसमें मलजल शोधन संयंत्र तथा निपटान कार्य भी शामिल हैं
- (iii) विद्युत भावित संयंत्र तथा सबस्टेशन जिसमें ग्रिड सबस्टेशन भी शामिल है
- (iv) गैस संस्थापनाएं तथा गैस वर्कस
- (v) टोस अपशिष्ट प्रबन्धन स्थल

VI. सार्वजनिक तथा अर्धसार्वजनिक उपयोग अंचल

(i) सरकारी कार्यालय, सरकारी प्रशासन केन्द्र, सचिवालय और पुलिस थाना

- (ii) शैक्षणिक, सांस्कृतिक और धार्मिक संस्थायें
- (iii) चिकित्सा स्वास्थ्य संस्थायें
- (iv) नागरिक / सांस्कृतिक और सामाजिक संस्थाए जैसे थियेटर, ओपेरा हाउस इत्यादि जो मुख्यतः गैर वाणिज्यिक किस्म के हों।
- (v) रक्षा से सम्बन्धित भूमि
- (vi) संचार टावर
- (vii) ढाबा, रैस्टोरैन्ट निम्न अनुसार:-

क्रम	सुविधाओं	क्षेत्र		क्षेत्र में	वाणिज्यिक	अधिकतम	फर्श क्षेत्र
संख्या	का नाम	न्यूनतम	अधिकतम	सुविधाओं की संख्या	घटक	भूतल आच्छादन	अनुपात
1.	ढाबा	500 वर्ग मीटर	1000 वर्ग मीटर	2	50 वर्ग मीटर	50 प्रतिशत	४० प्रतिशत
2.	रैस्टोरैन्ट	1000 ਕਸੀ ਸੀਟर	2000 वर्ग मीटर	2	10 प्रतिशत	30 प्रतिशत	150 प्रतिशत

- (viii) ईंधन स्टेशन
- (ix) कोई अन्य उपयोग, जिसे सरकार लोकहित में विनिश्चित करे।

VII. खुले स्थान

- (i) खेलकूद मैदान, स्टेडियम तथा खेल मैदान
- (ii) पार्क तथा हरित पटटी, बाग तथा अन्य मनोरंजनात्मक उपयोग
- (iii) कब्रिस्तान, शमशान घाट आदि
- (iv) निदेशक की अनुमित से सड़कों के साथ ईंधन स्टेशन, बस पंक्ति/शैल्टर
- (v) अनुसूचित सड़कों तथा मुख्य सड़कों के साथ हरित पट्टी में सार्वजनिक उपयोगिता सेवाएं जैसे इलैक्ट्रक ग्रिड स्टेशन प्रेषण लाईनें, संचार लाईनें, जल आपूर्ति लाइनें सीवरेज लाईनें, ड्रैनेज लाईनें।
- (vi) संचार टावर
- (vii) जल निकाय/झील/जल पुर्नभरण क्षेत्र
- (viii) मेला स्थल तथा बहु उपयोगी मैदान
- (ix) कोई अन्य उपयोग, जिसे सरकार लोकहित में विनिश्चित करें।

VIII. कृषि जोन

- (i) कृषि, बागवानी, डेरी और मुर्गी पालन
- (ii) आबादी देह में गांव घर
- (iii) अंचल विनियम XIX में निर्धारित निर्बन्धनों के अध्यधीन आबादी देह के बाहर फार्म हाऊस
- (iv) शिक्षण संस्थान
- (v) वन रोपण विकास तथा मनोरंजन के लिए उसका कोई भाग
- (vi) आबादी देह के समीप वर्तमान गांव का विस्तार यदि यह परियोजना, केन्द्र सरकार या राज्य सरकार द्वारा अनुमोदित या प्रायोजित हो
- (vii) दग्ध अवशीतन केन्द्र और पैरचयरीकरण केन्द्र
- (viii) बस अङ्डा और रेलवे स्टेशन
- (ix) अनिवार्य भवनों सहित हवाई अड्डा
- (x) बेतार केन्द्र
- (xi) निदेशक द्वारा अनुमोदित स्थलों पर अनाज गोदाम, भंडारण स्थल
- (xii) मौसम कार्यालय
- (xiii) भू-जल निकास और सिंचाई, पन बिजली केन्द्र और सिंचाई के लिए नलकूप
- (xiv) टेलीफोन और बिजली प्रेषण लाईनें ओर खम्भे
- (xv) खनन तथा उत्खनन कार्य जिसमें चूना तथा ईंटों के भट्टे, पत्थर खदानें और क्रेशिंग शामिल है जो नियमों तथा अनुमोदित स्थल पर, के अधीन रहते हुए है।

- (xvi) शमशान और कब्रिस्तान
- (xvii) ईंधन स्टेशन और सर्विस गैरेज
- (xviii) नवीकरणीय और गैर नवीकरणीय उर्जा शक्ति संयंत्र
- (xix) निदेशक के अनुमोदन से तरल पैट्रोलियम गैस भण्डारण गोदाम
- (xx) लघु उद्योग औद्योगिक इकाइयों को निम्नलिखित शर्तों की पूर्ति के अधीन रहते हुए अनुमित दी जाएगी, बशर्तें ऐसा स्थल रक्षा संस्थापनाओं, यदि कोई हो, के इर्द–गिर्द रक्षा संकर्म अधिनियम, 1903 (1903 का केन्द्रीय अधिनियम 7) के अधीन अधिसूचित वर्जित पट्टी के भीतर नहीं होना चाहिए।

क. स्थल मानदंड							
अंचल	मानदंड	मानदंड					
मध्यम संभावित क्षेत्र	शहरीकरण क्षेत्र से 2 किमी के भीतर (पैरिफिरल सड़कों को छोड़कर, यदि शहरी सीमा पर प्रस्तावित किया गया हो)	शहरीकरण क्षेत्र से 2 किमी से अधिक (परिधीय सड़कों को छोड़कर, यदि शहरी सीमा पर प्रस्तावित किया गया हो)					
	5 एकड़ तक गैर–प्रदूषणकारी हरी, नारंगी श्रेणी की लघु उद्योग इकाइयां।	किसी भी क्षेत्र की ग्रीन और नारंगी श्रेणी इकाइयां					
ख. पहुँच मानदंड							
क्षेत्र कि (27 पर कि कर हिंड	प्रोगिक उपयोग के लिए कृषि क्षेत्र में भूमि लिए न्यूनतम 30 फीट चौड़ा राजस्व सड़व या जाएगा । हालांकि, यदि भूमि उपयोग .5 फुट) चौड़ा राजस्व मार्ग/सार्वजनिक सड़ भूमि उपयोग में परिवर्तन अनुमति के लिए उ आवेदन करने वाले साइट के सामने 6 कर्म म (5.5 फुट) चौड़ी पट्टी का दान ग्राम बानैमा/उपहार के माध्यम से विस्तृत पट्टी गई भूमि ।	क/सार्वजनिक सड़क पर विचार की औद्योगिक परिवर्तन 5 करम इक पर दी गई है, तो उस सड़क आवेदन, इस शर्त पर माना जाएगा (33 फुट) परियोजना प्रत्यार्तक 1 पंचायत/स्थानीय प्राधिकरण को					

- (xxi) अनुसूचित सड़कों, राष्ट्रीय राजमार्ग तथा राज्य राजमार्ग के अलावा सार्वजिनक सड़क / रास्ता, जिसकी चौड़ाई 30 फुट से कम न हो, पर गैर प्रदूषणकारी मध्यम और बड़े पैमाने की कृषि आधारित उद्योग, बशर्ते कि स्थल ऐसी स्थापना, यदि कोई हो, के लिए यथा लागू सुरक्षा स्थापना के आसपास वर्जित पट्टी के भीतर नहीं होना चाहिए ।
- (xxii) निर्बन्धित / हरित पट्टी के बाहर क्षेत्र में राष्ट्रीय राजमार्ग / अनुसूचित सड़कों के साथ ढाबे, रैस्टोरैन्ट, मोटल, रिर्सोटज तथा मन बहलाव पार्क / थीम पार्क निम्न अनुसार होंगेः

क्रम	अनुज्ञय	क्षे	त्र	वाणिज्यक	अधिकतम	फर्श क्षेत्र अनुपात
संख्या	कि या	न्यूनतम	अधिकतम	घटक	भूतल	
	कलाप				आच्छादन	
1	2	3	4	5	6	7
1.	ढाबा	1000 वर्ग मीटर	1 एकड़	50 वर्ग मीटर	40 प्रतिशत	40 प्रतिशत
2	रैस्टोरैन्ट	2000 वर्ग मीटर	1 एकड़	15 प्रतिशत	30 प्रतिशत	150 प्रतिशत
3	बेंक्विट सुविधाओं सहित मोटल	2.5 एकड़	5 एकड़	15 प्रतिशत	30 प्रतिशत	150 प्रतिशत
4	रिर्सोट	४ एकड़	10 एकड़	15 प्रतिशत	30 प्रतिशत	150 प्रतिशत
5	मनोरंजन पार्क / थीम पार्क	2.5 एकड़	10 एकड़	15 प्रतिशत	30 प्रतिशत	50 प्रतिशत

परन्तु पहुंच अनुज्ञा यदि स्थल राष्ट्रीय राजमार्ग पर अवस्थित है, तो भारतीय राष्ट्रीय राजमार्ग प्राधिकरण तथा यदि स्थल अनुसूचित सड़क पर अवस्थित है, तो कार्यकारी अभियन्ता, लोक निर्माण विभाग (भवन तथा सड़कें) से प्राप्त की गई है।

(xxiii) बेंक्विट हालः

निम्नलिखित मानदंडों के अनुसार:-

अनुज्ञेय अचंल	कृषि अचंल
पहुंच	 पहुंच सड़क की चौड़ाई कम से कम 18 मीटर होनी चाहिए। यदि स्थल अनुसूचित सड़क पर स्थित है, तो इस रास्ते की अनुमित कार्यकारी अभियता, लोक निर्माण विभाग (भवन तथा सड़के) से अपेक्षित है। राष्ट्रीय राजमार्ग से भी पहुंच विचारी जा सकती है, यदि स्थल चौराहा / पहुंच मार्ग से न्यूनतम दूरी मानक पूरा करते हो तथा न्यूनतम 7 मीटर चौड़ी सेवा सड़क पर अवस्थित हो या आवेदक मारतीय राष्ट्रीय राजमार्ग प्राधिकरण (एन.एच.ए.आई.) से पहुंच की पूर्व अनुज्ञा प्रस्तुत करता है।
अपेक्षित क्षेत्र	न्यूनतम : 2.5 एकड़ आधिकतम : 5.00 एकड़
फर्श क्षेत्र अनुपात	50 प्रतिशत
भूतल आच्छादन	30 प्रतिशत
परिवर्तन प्रभार	वाणिज्यिक उपयोग के लिए विहित दर का 50 प्रतिशत
फर्श क्षेत्र अनुपात के भीतर अनुज्ञेय अनुषांगिक उपयोग	उपहार दूकान, एस.टी.डी. बूथ, खिलौना केन्द्र तथा फूलों की दूकानें इत्यादि के लिए अनुज्ञात फर्श क्षेत्र अनुपात का 10 प्रतिशत
पार्किग	स्थल क्षेत्र का न्यूनतम 25 प्रतिशत

टिप्पण:–

नगरपालिका सीमा के भीतर विवाह महल / बैंक्वेट हॉल का प्रावधान शहरी स्थानीय निकायों के विभाग द्वारा अनुमोदित तथा समय समय पर संशोधित नीति के अनुसार होगा।

- (xxiv) माईक्रोवेव स्तुप / स्टेशन, भुकम्प केन्द्र तथा दुरसंचार केन्द्र
- (xxv) संचार टावर
- (xxvi) सरकार या सरकारी एजेंसी द्वारा संविदा अथवा कार्य हेतू अल्पावधि के लिए लगाए जाने वाले तैयार मिश्रण कंकीट संयंत्र, वेट मिश्रण संयंत्र, गर्म मिश्रण संयंत्र इत्यादि।
- (xxvii) धर्म कांटा
- (xxviii) सर्विस गैरज, बिक्री / प्रदर्शन केन्द्र एवं सर्विस गैरज का विवरण निम्न अनुसार है:-

क्रम	सुविधा का	क्षेत्र	(एकड़)	वाणिज्यिक	अधिकतम	फर्श	पहुंच मार्ग	ऊँचाई
संख्या	नाम	न्यूनतम	अधिकतम	घटक	भूतल	क्षेत्र		
		•			आच्छादन	अनुपात		
1	सर्विस गैरज	0.5	1	शून्य	60 प्रतिशत	1.25	18 मीटर या सेक्टर सड़क के साथ सर्विस सड़क	18 मीटर
2	बिक्री / प्रदर्शन केन्द्र-एवं- सर्विस गैरज	0.5	2	अनुज्ञेय फर्श क्षेत्र अनुपात का 10 प्रतिशत	60 प्रतिशत	1.25	18 मीटर या सेक्टर सड़क के साथ सर्विस सड़क	18 मीटर

टिप्पणीः *वाणिज्यिक घटक के विषय में फीस तथा प्रभार वाणिज्यिक दरों पर उद्गृहीत किए जाएंगे; *विद्यमान/पहले से भूमि उपयोग परिवर्तन अनुमित प्राप्त सर्विस गैराज को बिकी/प्रदर्शन केन्द्र की अनुमति देने हेतु उपरोक्त मानदण्डों को पूर्ण करने की दिशा में ही विचार किया जाएगा।

कोई अन्य उपयोग, जिसे सरकार लोकहित में, विनिश्चित करे। (xxix)

प्राकृतिक संरक्षण जोन/आरक्षित पॉकेट/अनिर्धारित पॉकेट IX.

- कषि तथा बागवानी: (i)
- (ii) मत्स्य पालनः
- (iii) वन रोपण सहित सामाजिक वानिकी / पौधारोपण;
- सक्षम प्राधिकारी की अनुमति से क्षेत्र के 0.5 प्रतिशत से अनधिक निर्माण सहित क्षेत्रीय मनोरंजन (iv) गतिविधियां।

बिल्कूल निषिद्ध उपयोग X

उचित अनुज्ञप्ति के बिना पैट्रोलियम और अन्य प्रज्जवलनीय सामग्री का भंडारण।

परिशिष्ट-1

सूचना प्रौद्योगिकी उद्योग के स्कोप / परिभाषा में सिम्मिलित की गए उद्योगों की श्रेणियां

कम्प्यटर डिवाईसिस के अन्तर्गत: (क)

डैस्क्टाप

पर्सनल कम्पयुटरर्स

सरवर्स

वर्क स्टेशन

नोडस

टरमिनलस

नैटवर्क पी.सी.

होम पी.सी.

लैपटॉप कम्पयूटरर्स

नोट बुक कम्पयूटरर्स

पामटॉप कम्पयूटेंरर्स/पी.डी.ए.

नैटवर्क कंट्रोलर कॉर्ड/मेमोरी के अन्तर्गत: (ख)

नैटवर्क इन्टरफेस कार्ड (एन.आई.सी.)

एडोप्टर इथरनेट / पी.सी.आई. / ई.आई.एस.ए. / कोम्बो / पी.सी.एम.आई.सी.ए.

एस.आई.एम.एम.मेमारी

डी.आई.एम.एम.मेमोरी

सैन्ट्रल प्रोसैंसिग युनिट(सी.पी.यू.)

कन्ट्रोलर एस.सी.एस.आई. / ऐरं प्रोसैसर का प्रौसेसर / प्रोसैसर पावर मोडयूल / अपग्रेड

स्टोरेज यूनिटस के अन्तर्गत: (ग)

हार्ड डिसक ड्राईवस / हार्ड ड्राईवस

आर.ए.आई.डी. डिवाईसिस एवं उसके कन्ट्रोलर

फलोपी डिस्क डाईव

सी.डी.रोम डाईव

टेप ड्राईवस डी.एल.टी. ड्राईवस / डी.ए.टी.

आपटिकल डिस्क ड्राईव

अन्य डिजीटल स्टोरेज डिवाईज

(ঘ) अन्य :

की बोर्ड

मोनीटर

माऊस

मल्टीमीडिया किट्स

(ভ.) प्रिन्टर तथा आऊटपुट डिवाईसिस के अन्तर्गत:

डोट मैट्रिक्स

लेजरजेट

इन्कजैट

डेस्कजैट

एल.ई.डी. प्रिन्टर्स

लाईन प्रिन्टर्स

प्लाटर्स

पास बुक प्रिन्टर्स

(च) नेटवर्किंग उत्पाद के अन्तर्गतः

हब्ज

रूटर्स

स्विचिस

कोन्सनट्रेटर्स

ट्रांसरिसिवर्स

(छ) सोफटवेयर के अन्तर्गत :

एप्लीकेशन्स साफटवेयर

आपरेटिंग सिस्टम

मिडल वेयर / फर्म वेयर

(ज) कम्पयूटर सिस्टम के लिए लगने वाली पावर सप्लाई के अन्तर्गत :

स्विच मोड पावर सप्लाई

अनइन्टरप्टिड पावर सप्लाई

(झ) नेटवर्किंग / केबलिंग तथा उससे संबंधित उपकरण :

(सूचना प्रौद्योगिकी उद्योग से संबंधित)

फाईबर केबल

कोपर केबल

केबल्स

कनैक्टर्स, टरिमनल ब्लाक

जैक पैनल्स, पैच कोर्ड

माऊटिंग कोर्ड / वायरिंग ब्लाक

सरफेस माउंट बक्से

(ञ) कन्ज्यूमेबल्स के अन्तर्गत :

सी.डी.रोम/कम्पैक्ट डिस्क

फलोपी डिस्क

टैप्स डी.ए.टी. / डी.एल.टी.

रिबन्स

टोनर्स

इन्कजैट कारटेजिस

आऊटपुट डिवाईसिस को लगने वाली इंक

(ट) इलैक्ट्रोनिक कम्पोनेन्ट :

प्रिंटिड सर्किट बोर्ड / पापुलेटिड पी.सी.बी.

प्रिंटिड सर्किट बोर्ड / पी.सी.बी.

ट्रांजिस्टर्स

इन्टैग्रेटिड सर्किटस / आई.सी.एस.

डायोड्स/थाईरिस्टर/एल.ई.डी.

रेसिस्टर्स

केपेसिटर्स

स्विचिस (आन/आफ, पुश बटन्श, रोकर्स इत्यादि)

प्लगस/सोकेट्स/रिलेज

मेगनेटिक हेड्स, प्रिन्ट हैड्स

कनेक्टर

माईक्रोफोन्स / स्पीकर्स

फयुजिस

(ठ) टैलीकम्यूनिकेशन इक्वीपमेन्ट के अन्तर्गत :

टैलीफोन

विडियो फोन

फेसी माईल मशीन / फैक्स कार्ड

टैली प्रिन्टर/टैलेक्स मशीन

पी.ए.बी.एक्स. / ई.पी.ए.बी.एक्स. / आर.ए.एक्स. / एम.ए.एक्स. टैलीफोन एक्सचैंज

मल्टीप्लेक्सर्स / म्यूजिस

मोडम्स

टैलीफोन आन्सरिंग मशीन

टैलीकम्युनिकेशन्स स्वीचिंग एपरेटर्स

एन्टेना तथा मास्ट

वायरलैस डेटाकोम इक्वीपमेन्ट

रिसीविंग इक्वीपमेन्ट लाईक पेजर्स, मोबाईल / सैल्युलर फोन इत्यादि

वी.एस.ए.टीज.

वीडियो कोनफोरेंसिंग इक्वीपमेन्ट'

वीडियो एवं डिजिटल सिंगनलिंग के लिए लगने वाले सैट टाप बक्से के अन्तर्गत

(ढ) सूचना प्रौद्योगिकी को समर्थ बनाने वाली सेवायें वह व्यवसायिक किया तथा सेवायें है जिसके अन्तिम उत्पाद / सेवायें जिनको :

- भारत से बाहर वितरित करने के लिए
- संचार-जाल के लिए वितरित करने के लिए; तथा
- या तो बाहरी ठेके (बाहरी स्त्रोत) या उस कम्पनी के सुदूर गौण द्वारा उपलब्ध किया हुआ (बाहर अवस्थित

टिप्पण :-

सेवाएं जो इनमें शामिल नहीं हैं, :

- 1 सुदूर उत्पादन/विनिर्माण इकाइयां
- 2 कम्पनियों के निगमित कार्यालय अथवा उनकी स्थानीय शाखाएं
- 1 इन्टरनैट पर वास्तविक व्यवसाय

निम्नलिखित सेवाएं जो उपरोक्त दिये गये मापदण्ड पूर्ण करती हैं, उन्हें सम्मिलित होंगे :

- (i) बैंक ऑफिस आप्रेशन्स
- (ii) काल सैन्टरज़
- (iii) कोन्टैन्ट डिवैल्पमैन्ट अथवा एनीमेशन
- (iv) डाटा प्रोसैसिंग
- (v) अभियान्त्रिकी तथा रचना
- (vi) ज्योग्राफिक इन्फोरमेशन सिस्टम सर्विसिज
- (vii) मानव संसाधन सेवायें
- (viii) बीमा दावा प्रोसेसिंग
- (ix) लीगल डाटा बेस
- (x) मैडीकल ट्रान्सक्रिप्शन
- (xi) पे-रोल
- (xii) सुदूर रख-रखाव
- (xiii) राजस्व लेखाकरण
- (xiv) सपोर्ट सैन्टर
- (xv) वैब-साईट सर्विसेज

एस.एन. रॉय अपर मुख्य सचिव, हरियाणा सरकार, शहरी स्थानीय निकाय विभाग। अपूर्व कुमार प्रधान सचिव, हरियाणा सरकार, नगर तथा ग्राम आयोजना विभाग।

HARYANA GOVERNMENT

URBAN LOCAL BODIES DEPARTMENT

AND

TOWN AND COUNTRY PLANNING DEPARTMENT

Notification

The 8th June, 2020

No. CCP(NCR)FDP/BDR -BCA/2020 /502.-In exercise of the powers conferred by sub-section (7) of section 203C of the Haryana Municipal Act, 1973 (24 of 1973), for the area falling within limit of the Municipal Council, Bahadurgarh and sub- section (7) of section 5 of the Punjab Scheduled Roads and Controlled Areas Restriction of Unregulated Development Act, 1963 (Punjab Act 41 of 1963), for the area falling outside the limit of Municipal Council Bahadurgarh, with reference to Haryana Government, Urban Local Bodies Department and Town and Country Planning Department, notification No. CCP(NCR)/DDP/BDR-BCA/2019/1923 dated the 16th September, 2019, the Governor of Haryana hereby publishes the Final Development Plan 2041 A.D for bahadurgarh along with restrictions and conditions, given in Annexure A and B applicable to the controlled areas specified in Annexure B.

Drawings

- Existing Land Use Plan bearing Drawing No. DTP (JH) 15/99, dated the 29th June, 1999 (already published *vide* notification No. CCP (NCR)/JCA-1/2003/2523, dated the 30th October, 2003 in the Haryana Government Gazette, dated the 30th October, 2003).
- Existing Land Use Plan bearing Drawing No. DTP(JH)418/2012, dated the 02nd February, 2012 for part controlled Area number-IV around municipal limits of Bahadurgarh notified vide Haryana Government Gazette, notification No. CCP (NCR)/JJR/BGH/CA-4/A/2006/1423, dated the 13th June, 2006, published on 13th June, 2006
- Final Development Plan-2041 AD for Bahadurgarh Controlled Areas I, II, III and IV (part) bearing Drawing No. D.T.P. (JH) 620/2020, dated the dated 8th May, 2020.

Annexure-A

Explanatory note on the Final Development Plan Bahadurgarh-2041 AD for the controlled area I, II, III and IV (part).

I Historical Background:-

The Estate of Bahadurgarh alongwith 25 other villages were conceived by Bahadurkhan and Taj Mohammad of Faruknagar in Jagir in 1755 AD. The town was known as Sharafabad, when it was handed over to the Bahadurkhan and Taj Mohammad, who ruled it for over 40 years and built a fort here. The town and its dependent villages were bestowed upon to Mohammed Ismail Khan, brother of the Jhajjar Nawab by Lord Lake, Ismail Khan's family retained this Estate till 1857, the estate became part of the Rohtak District in the year 1860.

II Location and Regional Setting:-

Bahadurgarh town is situated on Delhi-Hisar National Highway number 9 at a distance of 37 Kilometres from Delhi. It is located between 76°-55'-25" East longitude and 28°-43'-50" North latitude. The Najafgarh town and Nangloi village, which are important settlements of National Capital Region (NCR) Delhi, are located at a distance of 10 Kilometres and 14 Kilometer respectively. The town of Bahadurgarh is very well linked with Delhi and other important towns of Haryana such as Rohtak, Hisar by National Highway No. 9 and Railway line.

III Physiography:-

Physiographical, the town is low lying and slopes towards South-East. The old settlement rests on a mound in the South-East. The trends of its development are along National Highway towards west and along Bahadurgarh-Najafgarh road, Bahadurgarh-Jhajjar road and across the Railway station in North. The Western Juan drain flows North to South in the middle of town and falls into Drain number 8 in Delhi. The underground water is brackish and in the year 2001, the canal based water supply has been launched. Since, the town is low lying, it is prone to floods.

IV Demographic profile:-

As per 1991 census, the town had a population of 57235 persons. The past trend of its population growth indicates that in spite of its closeness to Delhi, Bahadurgarh town could not achieve high growth rate due to its local problems of brackish underground water and weak urban infrastructure.

The decade-wise population of Bahadurgarh town since 1961 is as under:-

Population of Bahadurgarh Town

Year	Population	Decadal Percentage Growth
1961	14,982	-
1971	25,812	72.28
1981	37,488	45.23
1991	57,235	52.67
2001	1,31,925 (including vill	lage abadi in urbanisable area) 150.62
2011	1,84,540	39.90

The projected growth rate will be as under:

Year	Population	Growth rate
2011-2021	291573*	58%
2021-2031	463600*	59%
2031-2041	737124 say 737000*	59%

^{*}Projected population

V Economic Characteristics:-

The main problem of brackish water of this town has been solved now as the canal based water supply for the town has been commissioned recently. With the result, now the Industrial growth of the town has picked up. The Industrial base of this town is further going to be strengthened as some of the industries of non-conforming area of Delhi, which have been closed by the order of the Hon'ble Supreme Court of India, are also being set up at Bahadurgarh, being a nearest place of Delhi.

Land use proposals:-

The Bahadurgarh town has been proposed to be developed for population of 7.37 Lakh persons for 2041 AD. Description of different land uses is as under:-

Serial number	Land Use	Total Area (in Hectares)	Percentage of Total Area (%)	
1.	Residential	2356	39.17	
2.	Commercial	270	04.49	
3.	Industrial	1104	18.36	
4.	Transport and Communication	772	12.84	
5.	Public Utilities	230	3.83	
6.	Public and Semi Public uses	287	4.77	
7.	Park and Open Spaces	994	16.54	
	Total	6013	100.00	

Area of the existing town and villages falling in urbanizable Area=252 Hectare

Description of various land uses:-

1 Residential:-

The Final Development Plan-2041 AD of Bahadurgarh town has been designed for the projected population of 7.37 Lakh. In this Plan, an area of 2356 hectares has been reserved for residential purpose. The sector number 2, 6, 7, 9, 9A, 10, 11, 13 have already been developed by Haryana Shehri Vikas Pradhikarn (HSVP). Moreover, licenses for development of residential plotted/group housing colony have been granted in sector 3, 3A, 4A, 14, 15, 28, 28A, 29, 35, 36, 37. The residential sector shall be developed to the sector density indicated in the drawing with 20% variation on either side and in addition to it, the density as prescribed in the New Integrated Licensing Policy (NILP), Deen Dayal Jan Awaas Yojna Policy (DDJAY) and Affordable Group Housing policy. 20% Group Housing component policy will also be applicable in a residential sector.

Apart from the proposal to increase the density, the following provisions have also been made in the Development Plan:

(1) The additional area for infrastructure shall be provided in the already planned/ developed residential sectors to meet out the requirement of the additional population.

- (2) The minimum width of the roads in a residential colony / sector shall not be less than 12 meters.
- (3) The minimum area for parks /open spaces in a residential colony/ sectors shall be planned in such a manner that it shall meet the minimum norm of 2.5 sq. meters per person.

2 Commercial:-

In order to cater the commercial needs of Bahadurgarh town, an area of 270.00 hectares has been reserved for commercial purpose. An Auto Market has been developed along National Highway-9 in an un-organized way causing traffic jams and accidents. In order to solve this problem the said Auto-market has been proposed to be shifted to a new site, earmarked in sector-12. Sector 4 has been reserved for commercial sector in the mid of the town. Moreover, commercial pockets in sector 9, 12, 27, 35, 36, 38, 44 have been reserved. Besides this, all residential sectors would be developed on neighborhood planning concept, the local commercial needs of each sector would be accomplished within those sectors by developing local shopping centers.

3 Industrial:-

In this Final Development Plan, total area of 1104.00 hectare has been proposed under industrial use keeping in view the high demand of industrial land due to shifting of industries from Delhi. The Sectors 4B, 16, 17, 19 part, 21, 22 have already been developed by Haryana Shehri Vikas Pradhikaran/Haryana State Industrial and Infrastructure Development Corporation. Beside these sector no. 18, 18 A, 20 part, 23, 24 part, 33, 34, and 43 have also been proposed for the industrial purpose.

4 Transport and Communication:-

In the Final Development Plan 2041 AD, an area of 772.00 hectares has been proposed under Transport and Communication use. Bye – pass V-1 road 75 meter wide starting form sector-9 at National Highway number 9 and ends up again at National Highway 9 near sector-33 has already been developed and is functional. Another one northern periphery (V-2A) road 60 meter wide starting from Delhi territory above sector 23, 24, 44, 49, 50, 51, 47, 48 and 31 meeting with National Highway-9 near village Jakhoda has been proposed for smooth flow for traffic. For Intra-city traffic, a network of 60 meter and 45 meter wide roads on the grid iron pattern, have been proposed. Metro rail has already been constructed and is functional up to Sector-6. Metro rail along National Highway-9 in the Northern side green belt has been proposed up to controlled area boundary under this development plan.

Bahadurgarh is basically an industrial town. An area of 47 hectare has been proposed in sector 17A for railway yards, railway station and siding, roads transports depots and parking areas. A pocket of an area of 19.0 hectare has been proposed in sector 38 for transport and communication purposes. Sector 32 earlier reserved for Transport and Communication Zone in Final Development Plan Bahadurgarh 2031AD which has now been proposed as industrial zone in view of the increased demand for industrial purpose and potential of the area. A pocket of 89.50 hectare has also been proposed for Transport and Communication as sector 32 on west of sector 33. The hierarchy of the right of way of major roads has been proposed as under:

Serial number	Classification	Name of roads	Land reservation	
1	V-1	Bye Pass	75 Meter wide road along with 100 meter green belt on both sides.	
2	V-1A	Rohtak-Delhi National Highway number-9	Existing width along with 60 meter wide green belt on both sides.	
3	V-2	Sector dividing road	60 Meter wide.	
4	V-2 A	Periphery road	60 Meter wide road along with 30 meter green belt on both sides.	
5	V-2 b	Periphery road	60 Meter wide road along with 30 meter green belt on outer sides.	
6	V-2 C	Bahadurgarh-Jhajjar, Bahadurgarh-Sidipur, road Bahadurgarh-Badli	60 Meter wide along with 30 meter green belt on both sides.	
7	V-3	Sector dividing road	45 Meter wide road.	
8	V-3 A	Bahadurgarh-Najafgarh, Bahadurgarh-Nahra raod	Existing width to be widened upto 45 meter wide.	
9	V-3 B	Sector dividing road	30 Meter wide road (Developed road).	

5 Public Utility Zone:-

In order to cater to the needs of projected population of 7.37 Lakh persons an area of 230.00 hectares has been reserved for public utility uses. The area reserved under public utility use has been proposed in sectors 7, 17, 22A, 23, 30, 33, 36, 37, 38, 44 and 49 and in agricultural zone. Earlier, in the Final Development Plan Bahadurgarh 2031AD above sector-29, a pocket was reserved for public utility zone which has now been planned for residential purpose for better planning.

6 Public and Semi-Public Use Zone:-

In the Regional Plan of National Capital Region, Bahadurgarh town has been identified as a Delhi Metropolitan Area town and as per recommendations of the said plan; Bahadurgarh town would accommodate the offices and institutions of Public and private sector enterprises, which would be shifted out of Delhi for the decongestion of National Capital. Keeping in view the aforesaid proposal, an area of 287.00 hectares has been proposed to be developed as Public and Semi Public uses in the Final Development Plan. These Public and Semi-Public uses would also accommodate town level community facilities such as Technical Colleges, Technical Training Institutes, Medical Institutes, Hospitals, Fire Station and Government Offices etc. The area reserved under Public and Semi Public Use is proposed in sectors 3A, 5, 7, 10, 12, 13, 14, 19, 30, 31, 38, 45 and 50.

7. Open Spaces and Green Belts:-

The 994.00 hectare area has been proposed under open spaces and green belts. Sector 5 (Part) has been earmarked for town level park with an area of 37 hectares. Areas of 7.00 hectare and 5.00 hectare have also been proposed for parks in sector 7 and 11 respectively. An area of 6 hectare has been proposed for stadium and play ground in sector -11. Sector 39, 12 A and 22A part also reserved under open spaces. Area of 9.00 hectare and 13 hectare in sector 44 and 46 respectively has also been proposed for parks, sports ground, stadium. A site of 2.00 hectare has been proposed for Stadium in Haryana Shehri Vikas Pradhikaran acquired land in sector 37. Beside this green belts along roads, railway track and drains/canal have also been proposed as shown in the plan.

8. Natural Conservation Zone / Water Conservation Area:-

Natural Conservation Zone (NCZ) are major natural features, identified as the environmentally sensitive areas in Regional Plan-2021 AD, wherein activities like Agriculture & Horticulture, Pisiculture, Social Forestry/Plantation including afforestation and Regional Recreational Activities with no construction exceeding 0.5% of the area with the permission of the competent authority are allowed. In order to identify the Natural Conservation Zone, the ground truthing exercise has been carried out. Further, the matter is also under consideration in Hon'ble National Green Tribunal in OA No. 147 of 2014 titled as Legal Aid Committee, National Green Tribunal Bar Association Vs. MoEF and others. Hence, the orders of Hon'ble NGT dated 20.11.2019 & 20.03.2020 and any subsequent decision later on, in the matter of Natual Conservation Zone will be applicable and, in case, any site is finalized as NCZ, then the provisions of Natural Conservation Zone will be applicable over that area irrespective of the proposals given in the plan.

9 Agricultural:-

The remaining area in the controlled area is kept as agriculture zone. This will however not prevent the essential building development within this area such as the extension of existing villages contiguous to Abadi-deh, if undertaken as a project sponsored or approved by the Government and other activities included as permissible activities in the Zoning regulations under appendix 'B' to annexure 'B' ancillary and allied facilities necessary for the maintenance and improvement of this area as agricultural land which is proposed to serve as an open country side for the town as a whole. Approximately, 10 Hectares of area has been earmarked for dairy farming, which are to be shifted from the old town on Sidipur road.

Zoning Regulations:-

The legal sanctity to the proposal regarding land use is being given to the effect by a set of zoning regulations (Annexure B) which form a part of this development plan. These regulations will govern the change of land use and standards of development. They also very elaborately detail out allied and ancillary uses which will be permitted in the various major land uses and stipulate that all change of land use and development shall be in accordance with the details shown in the master plan thereby ensuring the preparation of detailed sector plans for each sector to guide the development and enforce power controls.

ANNEXURE- B

Governing use and development of land in the Controlled Areas of Bahadurgarh as shown in Final Development Plan Drawing No DTP (JH) 620/2020, dated the 8th May, 2020.

- **1. General:-** These Zoning Regulations, forming part of the Development Plan for the Controlled Areas Bahadurgarh shall be called Zoning Regulations of the Development Plan for the Controlled Areas Bahadurgarh.
 - (1) The requirement of these regulations shall extend to the whole of the area covered by the development plan and shall be in addition to the requirements of the Punjab Scheduled Roads and Controlled Areas Restriction of Unregulated Development Act, 1963 (Punjab Act 41 of 1963) and the rules framed there under.

II. Definitions:-

In these regulations:-

- (a) "approved" means approved under the rules;
- (b) "building rules" means the rules contained in part VII of the rules;
- (c) "Drawing" means Drawing No. DTP (JH) 620/2020, dated the 8th May, 2020
- (d) "Building Code means" the Haryana Building Code 2017.
- (e) Floor area ratio (FAR)" means a quotient obtained by dividing the multiple the total covered area of all floors and hundred, by the area of plot i.e.

For the purpose of calculating FAR, cantilevered permitted roof projections, lift room, mumty, balcony, basement if used for parking, services and storage, stilt area (unenclosed) proposed to be used for parking and pedestrian plaza only, open staircase (without mumty), open court yard of permitted size shall not be counted towards FAR:

Provided that area under shaft, chutes, lift well and staircase from stilt to next floor shall be counted towards FAR only at once on ground floor:

Provided further that in case the ventilation shaft area is more than three square metres, it shall not be counted in FAR;

- (f) 'Fuel station' means the fuel filling station providing retail supply of fuel for automobiles which shall include petrol pumps, CNG station, bio-fuels, charging stations, battery providing stations etc.
- (g) Group Housing" means a building designed and developed in the form of flats for residential purpose or any building ancillary to group housing'
- (h) 'Light Industry' means industry not likely to cause injurious or obnoxious noise, smoke, gas, fumes or odors, dust, effluent and any other nuisance to an excessive degree and motivated by electric power.
- (i) 'Local Service Industry' means an industry the manufacture and product of which is generally consumed within the local area for example: bakeries, ice-cream manufacturing aerated water, atta chakkies with power, laundary, dry cleaning and dyeing repair and service of automobile, scooters and cycles, repair of household utensils, shoe making and repairing, fuel depots etc. provided no solid fuel is used by them.
- (j) 'Medium Industry' means all industries other than Light Industry and Local Service Industry and not omitting obnoxious or injurious fumes and odours.
- (k) 'Extensive Industry' means an industry set up with the permission of the Government and is extensive, employing more than 100 workers and may use any kind of motive power of fuel provided they do not have any obnoxious features.
- (l) 'Heavy Industry' means an industry to be set up in public or semi public or private sector with the permission of the Government (The cost of plant machinery etc. as defined in the industrial policy of the Government);
- (m) 'Obnoxious or Hazardous Industry' means an industry set up with the permission of the Government and is highly capital intensive associated with such features as excessive smoke, noise, vibration, stench, unpleasant or injurious effluent, explosive, inflammable material etc. and other hazard to the health and safety of the community.

(n) 'Material Date' means the date of publication of notification of various controlled areas declared as under :-

Serial number	Controlled area	Material date
1	Controlled Area around municipal Bahadurgarh notified <i>vide</i> Punjab Government Gazette Notification No. 3959-2TCP-64/29556, dated the 7th November, 1964 published on 26th February, 1965.	26th February, 1965
2	Additional Controlled Area around Bahadurgarh notified <i>vide</i> Haryana Government Gazette notification No. 4779-10DP-84/9720, dated the 25th June, 1984, published on 10th July, 1984.	10th July, 1984
3	Additional Controlled Area number-III Bahadurgarh notified <i>vide</i> Haryana Government Gazette notification No.CCP-96/8681 dated 12th June, 1996, published on 18th June, 1996.	18th June, 1996
4	Controlled Area around municipal limits of Bahadurgarh notified <i>vide</i> Haryana Government Gazette notification No. CCP (NCR)/JJR/BGH/CA-IV/A/2006/1423 dated 13th June, 2006, published on 13th June, 2006	13th June 2006

- 'Non Confirming Use' in respect of any land or building in a controlled area means the existing use of (0)such land or building which is contrary to the major land use specified for that part of the area in the Final Development Plan.
- Public Utility Service' building means any building required for running of public utility services such (p) as water supply, drainage, electricity, post and telegraph and transport and for any municipal service including a fire station.
- 'Rules' means the Punjab Scheduled Roads and Controlled Areas Restriction of Unregulated (q) Development Rules, 1965 and the rules framed under the Haryana Municipal Act, 1973;
- 'Sector Density', 'Colony Density' and 'Town Planning Scheme Density' shall mean the number of (r) persons per hectares in sector area, colony area or Town Planning Scheme, as the case may be;
- Sector Area', 'Colony Area' and 'Town Planning scheme area' shall mean the area of the sector or (s) colony or of the scheme as bounded within the major road system shown on the drawing and /or as shown in the approved layout of the sector/ colony/scheme; Explanation:-
 - In this definition the 'Sector Area' or 'Colony Area' or 'Town Planning Scheme Area' (1)shall mean the area of the Sector/ Colony/ Town Planning Scheme as shown on the drawing or on the approved layout plan of the Colony/Sector/ Town Planning Scheme which will be excluding the area unfit for building development within the sector or the colony or the scheme as the case may be;
 - Benefit of 50% of the area falling under major roads and their adjoining green belts, if (2) any, shall be allowed for plotable area/floor area ratio (FAR) in case of plotted/group housing colony;
 - In the layout plan of Town Planning scheme, colony or sector, other than industrial (3) scheme/colony/sector, the land reserved for roads, open space, schools, public and community building and other common uses shall not be less than 45% of the gross area of the land under the Town Planning scheme/colony/sector;
 - **(4)** For the purposes of calculation of sector density or colony density it shall be assumed that 55 percent of the sector area or colony area will be available for residential plots including the area under Group housing and that every building plot shall on the average contain three dwelling units each with a population of 4.5 persons per dwelling unit or 13.5 persons per building plot or as incorporated in the zoning plan of the colony/group housing complex. In the case of shop-cum-residential plot however, only one dwelling unit shall be assumed.
 - (5) Notwithstanding above, the projects approved under specific policy like New Integrated Lincencing Policy; Floor Area Ratio and Density shall be the governing parameters instead of plotable area.
- 'Site Coverage' means ratio expressed in percentage between the area covered by the ground floor of (t) building and the area of the site;

- (u) The term "Act", "Colony" "Colonizer" "Development plan", "Sector", 'Scheme' and "Sector Plan", shall have the same meaning as assigned to them in the Punjab Scheduled Roads and Controlled Areas Restriction of Unregulated Development Act, 1963 (Punjab Act 41 of 1963) and rules, 1965 and the Haryana Municipal Act, 1973 (24 of 1973) and the rules framed there under.
- (v) 'Farm House' means a house constructed by the owner of a farm at his land for the purpose of:
 - (i) Dwelling unit, i.e. main use,
 - (ii) Farm shed i.e. Ancillary use.

Notes:-

- (1) The construction of the farm house shall be governed by the restrictions given under clause XIX regarding "provision of farm houses outside adadi- deh in agricultural zone".
- (2) The farm sheds shall be governed by the restriction mentioned in clause XIX regarding building control and site specifications.
- (w) 'Ledge or Tand': mean a shelf-like projection, supported in any manner whatsoever, except by means of vertical supports within a room itself but not having projection wider than one metres;
- (x) "Loft" shall mean an intermediate space between two floors on a residual space with maximum height of 1.5 metres and which is constructed or adopted for storage purposes only;
- (y) "Mezzanine floor" means an intermediate floor, between two floors, with area restricted to ½ (half) of the area of the lower floor and with a minimum height of 2.3 metres and shall not be lower than 2.3 metres (clear height) above floor level;
- (z) 'Subservient to Agriculture':- mean development and activities, which are required to assist in carrying out the process of "agriculture" such as tubewells, pump chambers, wind mills, irrigation drains, pucca platform, fencing and boundary walls, water hydrants etc;
- (za) "Small Scale Industries" means Industrial unit, which is registered as Small Scale Industry by the Industries Department.
- (zb) "Agro based Industries" means an industrial unit, which uses food grains, fruits or Agro waste as raw-material;
- (zc) "Information Technology Industrial Units" means the categories of industries included in the Annexure to the Government of Haryana Information Technology Policy, 2000 and in Appendix-1 to this notification and/or, as may be defined by the Government of Haryana from time to time;
- (zd) "Cyber Park/ Information Technology Park" means an area developed exclusively for locating software development activities, and Information Technology Enabled services wherein no manufacturing of any kind (including assembling activities) shall be permitted;
- (ze) "Cyber City" means self contained intelligent city with high quality of infrastructure, attractive surrounding and high speed communication access to be developed for nucleating the Information Technology concept and germination of medium and large software companies Information Technology Enabled services; wherein no manufacturing units may be allowed;
- (zf) Green belts means those belts of lands which have been sound along the sector/periphery road in development plan which is used for widening of roads specific in future.
- (zg) Any other term shall have the same meaning as assigned to it in the Punjab Scheduled Roads and Controlled Areas Restriction of Unregulated Development Act, 1963, (Punjab Act 41 of 1963) and the rules 1965 and the Haryana Municipal Act, 1973 (24 of 1973) and the rules framed thereunder;

III. MAJOR LAND USES/ZONE:-

- 1. (i) Residential Zone
 - (ii) Commercial Zone
 - (iii) Industrial Zone
 - (iv) Transport and Communications Zone
 - (v) Public Utility Zone
 - (vi) Public and Semi-Public Zone
 - (vii) Open Spaces Zone.
 - (viii) Agriculture Zone.
 - (ix) Natural Conservation Zone/Reserved Pocket.

2. Classification of major land uses is according to Appendix ' A'.

IV. DIVISION INTO SECTORS:-

Major land uses mentioned at serial numbers (i) to (vii) in zoning regulation-III above, which are land uses for building purposes, have been divided into sectors as shown on the concerned development plan drawing and each sector shall be designated by number as indicated on the drawing.

V. DETAILED LAND USES WITHIN MAJOR USES:-

Main ancillary and allied uses, which are subject to the other requirements of these regulations and of the rules, may be permitted in the respective major land use zone are listed in Appendix B sub-joined to these zoning regulations.

VI SECTOR NOT RIPE FOR DEVELOPMENT:-

Notwithstanding the reservation of various sectors for respective land uses for building purposes, the Director may not permit any changes in their land use or allow construction of building thereon from considerations of compact and economical development of the controlled area, till such time as availability of water supply, drainage arrangement and other facilities for the sectors are ensured to his satisfaction.

VII SECTORS TO BE DEVELOPED EXCLUSIVELY THROUGH GOVERNMENT ENTERPRISES:-

Government may notify any sector for development exclusively by it or by its agencies, in which case, no further permission for change of land use or grant of licence shall be permitted in such sectors.

VIII. LAND RESERVATION FOR MAJOR ROADS:-

(1) Land reservation for major roads marked in the Drawing shall be as under:-

Serial	Classification	Name of roads	Land reservation	
number				
1	V-1	Bye Pass	75 Meter wide road along with 100	
			meter green belt on both side.	
2	V-1A	Rohtak-Delhi National Highway	Existing width along with 60 meter	
		number-9	wide green belt on both side.	
3	V-2	Sector dividing road	60 Meter wide.	
4	V-2 A	Periphery road	60 Meter wide road along with 30	
			meter green belt on both side.	
5	V-2 b	Periphery road	60 Meter wide road along with 30	
			meter green belt on outer side.	
6	V-2 C	Bahadurgarh-Jhajjar,	60 Meter wide along with 30 meter	
		Bahadurgarh-Beri, Bahadurgarh-	green belt on both side.	
		Sidipur, Bahadurgarh-Badli road		
7	V-3	Sector dividing road	45 Meter wide road.	
8	V-3 a	Bahadurgarh-Najafgarh,	Existing width to be widened upto	
		Bahadurgarh-Nahra road	45 meter wide.	
9	V-3 B	Sector dividing road	30 Meter wide road (Developed	
			road).	

- (2) Width and alignment of other roads shall be as per sector plans or as per approved layout plans of colonies.
- (3) Benefit of only 50% of the area falling under major roads and adjoining green belts, if any, shall be allowed towards plotable area/ floor area ratio in the Plotted/Group Housing Colony, while approving the layout plans for the sector/colony to be developed by Haryana Shehri Vikas Pradhikaran and private colonizers. In case of commercial colony and information Technology park/cyber city the benefit of 10% of Floor area ratio of the total area of the site or area falling under green belt and sector roads whichever is less shall be allowed.
- (4) Benefit of tradable FAR, may be allowed against licences granted for the land falling under sector road or green belt and open space zones in accordance with specified policies;

IX. Non confirming uses either existing or having valid Charges of land use permission:-

1. With regard to the existing industries shown in the zones other than industrial zone in the development plan, such industrial non-conforming uses shall be allowed to continue for a fixed period to be determined by the Director, but not exceeding ten years, provided that the owner of the industry concerned:

- (a) Undertakes to pay to the Director, as determined by him the proportionate charges, toward, the external development of the site as and when called upon by the Director to do so in this behalf;
- (b) During the interim period makes satisfactory arrangement for discharge of effluent to the satisfaction of the Director.
- (c) Shall not be allowed to expand the existing project within the area of non-conforming use.
- 2. With regard to the projects having valid Change of land use permission and located in the zones other than confirming use zone in the development plan, such non-conforming uses shall be allowed to continue, provided that the owner of the building concerned.
 - (a) undertakes to pay to the Director, as determined by him the proportionate charges, toward, the external development of the site as and when called upon by the Director to do so in this behalf; and.
 - (b) During the interim period makes satisfactory arrangement for discharge of effluent to the satisfaction of the Director.

X. DISCONTINUANCE OF NON-CONFORMING USES:-

- (1) If a non-conforming use of land has remained discontinued continuously for a period of two years or more, it shall be deemed to have terminated and the land shall be allowed to be re-used or re-developed only according to the conforming use.
- (2) If a non-conforming use building is damaged to the extent of fifty percent or more of its re-production value by fire, flood, explosion, earthquake, war, riot or any other natural calamity, it shall be allowed to be re-developed only for a conforming use.
- (3) After the discontinuance of projects included under clauses IX, the land shall be allowed to be redeveloped or used only for conforming use.
- (4) After a lapse of period fixed under clause IX (1) the land shall be allowed to be re-developed or used only for conforming use.

XI THE DEVELOPMENT TO CONFORM TO SECTOR PLAN AND ZONING PLAN:-

Except as provide in regulation IX, no land within major land use shall be allowed to be used and developed for building purposes unless the proposed use and development is according to the details indicated in the sector plan and zoning plan or the approved colony plan in which the land is situated.

XII. INDIVIDUAL SITE TO FORM PART OF APPROVED LAYOUT OR ZONING PLAN:-

No permission for erection or re-erection of building on a plot shall be given unless:-

- (i) the plot forms a part of an approved colony or the plot is in such area for which relaxation has been granted as provided in regulation XVII; and
- (ii) the plot is accessible through a road laid out and constructed up to the situation of the plot to the satisfaction of the Director.

XIII. MINIMUM SIZE OF PLOTS FOR VARIOUS TYPES OF BUILDINGS:-

The minimum size of the plots for various types of uses shall be as below:-

(i)	Residential plot	50 square meters
(ii)	Residential plot on subsidised industrial housing or slum dwellers housing scheme approved by the Government.	35 square meters
(iii)	Shop-cum-residential plot	100 square meters
(iv)	Shopping booths including covered corridor or pavement in front.	20 square meters
(v)	Local service industry plot	100 square meters
(vi)	Light Industry plot	250 square meters
(vii)	Medium Industry Plot	8000 square meters

(2) The area norms for Group Housing Colony, plotted residential colony and commercial colony shall be in accordance with the policies specified from time to time for residential and commercial development. However, in a case group housing scheme is floated by Haryana Shehri Vikas Pradhikaran or any other Government Agency, the size of group housing site shall be as specified in the scheme;

XIV. SITE COVERAGE/ HEIGHT AND BULK OF BUILDING UNDER VARIOUS TYPES OF BUILDINGS:-

The site coverage, Floor Area Ratio and height permitted on a specific plot/site shall be governed by the prescribed policy parameters, building code/rules and /or as laid down in the zoning plan of such plot/site.

XV. BUILDING LINES IN FRONT SIDE AND REAR OF BUILDING:-

These shall be provided in accordance with building code/rules and /or as laid down in the zoning plan of such site.

XVI. ARCHITECTURAL CONTROL:-

Wherever architectural control is considered necessary, every building shall conform to architectural control prepared as per clause 6.4 of Harvana Building Code 2017.

XVII. RELAXATION OF AGRICULTURAL ZONE:-

In the case of any land lying in Agriculture zone, Government may relax the provisions of this development plan:-

- (a) for use and development of the land into a residential or industrial colony provided the colonizer has purchased the land for the said use and development prior to the material date and the colonizer secures permission for this purpose as per rules.
- (b) for use of land as in individual site (as distinct from an industrial colony).

Provided that:-

- (i) the land was purchased prior to the material date;
- (ii) the Government is satisfied that the need of the industry is such that it cannot await alternative allotment in the proper zone;
- (iii) the owner of the land secures permission for building as required under the rules and
- (iv) the owner of the land undertakes to pay to the Director as determined by him, the proportionate charges as and when called upon by the Director in this behalf and during the interim period makes satisfactory arrangement for discharge of effluent.

Explanation:-

The word 'purchase' used in this regulation shall mean acquisition of full proprietary rights/lease right for such period as may be specified by the Government for different purposes etc.

XVIII. DENSITY:-

Every residential sector shall be developed to the sector density indicated in the drawing with 20% variation on either side and in addition to it, the density as prescribed in the New Integrated Licensing Policy (NILP), Deen Dayal Jan Awaas Yojna Policy (DDJAY) and Affordable Group Housing policy, 20% Group Housing component policy will also be applicable in a residential sector.

XIX. PROVISION OF FARM HOUSE OUTSIDE ABADI- DEH IN AGRICULTURAL ZONE:-

Farmhouses shall be allowed only for bonafide use of landowner(s) provided he does not own a house in any urban area because the real object for allowing farmhouses in agriculture zone is to meet the housing needs of the farmers on a small portion of the farm so that he can take care of his agriculture produce while living on that farm. Hence, a farm house in agriculture zone, outside abadi-deh may be allowed if the area of the land is 2 acres or more on the following conditions:-

	Size of farm house	Main building of the dwelling unit	Ancillary building of main dwelling
		dwening unit	unit uwening
(i) Site Coverage	2 Acres minimum but CLU permission for the area falling under road reservation /proposed road widening as per Development Plan, shall not be considered. However the net area should not be less than 1.5 acres after excluding the area falling under the green belt/restricted belt and falling in Agriculture zone from applied area	As applicable to residential plot equivalent to 250 sq.yds	1 percent of the farm land (not more than 40% shall be used for labour/servant quarters)
	of 2 acres.		

Upto 3 acres	As applicable to residential plot equivalent to 375 square yards.	-do-
Upto 4 acres and above	As applicable to residential plot equivalent to 500 square yards.	-do-
(ii) Height and Storey	11 metres, three storeyed	4 metres, single Storey.

(iii) SET BACK:-

It shall be at least 10 meters away from the edge of the agricultural land on all sides provided that if land attached to the farm house abuts a road, the house shall be constructed with a minimum set back from the edge of the road as under:

(a) Where the road is bye pass to a Scheduled Road. 100 metres.

(b) Where the road is a Scheduled Road 30 metres or as shown in the

Development Plan

(c) Any other road. 10 meters.

(iv) APPROACH ROAD:-

Any revenue rasta/ road as defined in the revenue record.

(v) BASEMENT:-

Basement shall be permitted to the maximum extent of ground floor coverage and uses are permitted as per the Harvana Building Code-2017.

(vi) LEDGE, LOFT AND MEZZANINE FLOOR:-

Ledge, loft and mezzanine floor shall be permitted within the building subject to the restrictions above as well as the restrictions stipulated in the definition given in clause –II of zoning regulations of Development Plan.

(vii) SERVICE WATER SUPPLY AND DRAINAGE:-

- (a) Good potable water supply should be available in the farm for human consumption in case of farm house is built.
- (b) Open sanitary drains or covered drains to be provided to clean the sheds in case of Dairy farms, Drains are to be provided for carrying rain water in case of all buildings.
- (c) Septic tank to be provided for disposal of human and animal waste as per provisions of Rules.
- (d) The distance between the septic tank and open well or tubewell shall be as provided in the Rules.
- (viii) The owner shall be permitted to construct boundary wall around the main dwelling unit and ancillary portion thereof and around remaining area of farm barbed wire fencing shall be allowed.
- (ix) The Change of Land Use permissions for setting up of farmhouse shall be considered in the area other than over exploited or critical areas as declared by Central Ground Water Board.

Provided that Government may amend the minimum size of the farm for any scheme sponsored by the State Government/State Agency for the proper utilization of the rural zone.

XX. PROVISION OF INFORMATION TECHNOLOGY UNITS AND CYBER PARKS/ CYBER CITIES:-

(i) LOCATION:-

- (a) Information Technology Industrial Units will be located in Industrial Areas/Industrial Zones only;
- (b) Cyber Parks/Information Technology Parks will be located either in Industrial Areas or Industrial abutting sector roads in the form of integrated development. However, no manufacturing units will be permitted in such parks.
- (c) Cyber Cities: The location of such a facility will be decided by the Government.

(ii) SIZE :-

Serial number	Туре	Size
1	Information Technology Industrial Unit	1 to 5 acres
2	Cyber Park/Information Technology Park	5 to 15 acres
3	Cyber City	Minimum 50 acres

(iii) MISCELLANEOUS:-

I. Parking:-

Parking will be as per the provisions of the Haryana Building Code, 2017 as amended from time to time.

II. Other Activities:-

- (a) Incidental commercial activities like Banks, Restaurants, Insurance Offices etc. shall be permitted subject to restriction of 4% of the gross area of the Cyber Park/Information Technology Park;
- (b) Only 5% of the area of the Cyber City shall be allowed for Group Housing and 4% of the total area of the Cyber City shall be permitted for Commercial/Institutional uses.
- (c) No residential plotted development shall be allowed in a Cyber City;
- (d) For a Cyber City Project if allowed in Agricultural Zone, the entrepreneur shall make the arrangement of water supply and other facilities like sewerage disposal/drainage etc;
- III. The Government may impose any other condition as deemed necessary from time to time.

XXI SETTING UP OF COMMUNICATION TOWERS:-

Permission of Mobile Towers within the Controlled area shall be granted as per the policy instructions of Department's memo dated 10.03.2015 and as amended from time to time.

XXII SAFETY AGAINST SEISMIC HAZARDS:-

As the Development Plan area falls in Zone IV as per Seismic Zone map of Indian Standard IS 1893:2002 and hence is considered as High Risk Zone. In order to take care of the same "the whole urban development shall be checked for safety against intensity "VIII" probability of occurrence, and upgraded for required seismic resistance in buildings and infrastructure as found necessary".

XXIII BRICK KLINS IN CONTROLLED AREAS:-

Siting of the brick kilns in the Controlled Areas shall be governed by the respective policy/ guidelines issued by the Competent Authority from time to time.

XXIVRELAXATION OF DEVELOPMENT PLAN:-

Government may in case of hardship or with a view to save any structure constructed before the material date, relax any of the provisions of the development plan on principles of equity and justice on payment of such development charges and on such other conditions as it may deem fit to impose.

APPENDIX A CLASSIFICATION OF LAND USES

Main code	Sub code	Main group	Sub group
code	code		
100		Residential	Residential Sector on neighborhood pattern
200		Commercial	
	210		Retail Trade
	220		Wholesale Trade
	230		Warehousing and Storage
	240		Office and Banks including Government Office
	250		Restaurants, Hotels and Transient Boarding Houses including public assistance institutions providing residential accommodation like Dharamshala, Tourist House etc.
	260		Cinema and other places of public assembly on a commercial basis.
	270		Professional Establishments

Main code	Sub code	Main group	Sub group
300		Industrial	
	310		Service Industry
	320		Light Industry
	330		Extensive Industry
400		Transport and Communication	
	420		Roads, road transport depots and parking areas, fuel station and garage
	450		Telephone Exchanges, Telegraph offices etc
	460		Broadcasting Station
	470		Television Station
500		Public Utilities	
	510		Water Supply installation including treatment plants
	520		Drainage and Sanitary installation including Sewage Treatment Plant and disposal works
	530		Electric power plants substation etc.
	540		Gas Installation and Gas work.
	550		Solid Waste Management sites.
600		Public and semi public	
	610		Government Administrative Central Secretariat District Offices, Law Courts, Jails, Police Stations, Governors and President's Residence.
	620		Education, Cultural and Religious Institutions
	630		Medical and Health Institutions
	640		Cultural institution like Theatres, Opera Houses etc. of a predominantly non commercial nature
700		Open Spaces	
	710		Sports Grounds, Stadium and Play Grounds
	720		Parks
	730		Green Belts, Garden and other Recreational Uses.
	740		Cemetreies, crematories etc
	750		Fuel stations and Bus queue shelters
	760		Water Bodies/lakes
800		Agricultural land	
	810		Market garden
	820		Orchards and nurseries
	830		Land under staple crops
	840		Grazing and land pastures
	850		Forest land
	860		Marshy land
	870		Barren land
	880		Land under water
	890		Diary farming
1000		Natural Conservation	Agriculture and Horticulture
		Zone/Reserved Pockets	Pisiculture
			Social Forestry, afforestation and
			Regional Recreational activities with construction not exceeding
			0.5% of the area with the permission of the competent authority.

APPENDIX B

The permissible activities given under main land uses shall be allowed in accordance with the policy/parameters approved by the Government and/or at sites as approved by the Competent Authority in the Sector/Colony/Scheme Plan.

I RESIDENTIAL ZONE

- (i) Residence
- (ii) Social community religious and recreational buildings
- (iii) Public utility buildings.
- (iv) Educational buildings and all types of school and college where necessary.
- (v) Health institutions.
- (vi) Cinemas
- (vii) Commercial and professional offices.
- (viii) Retail shops and restaurants, Dhaba,
- (ix) Local service industries.
- (x) Fuel stations.
- (xi) Bus stops, tonga, taxi, scooter and rickshaw stand.
- (xii) Nurseries and green houses.
- (xiii) Any other minor needs to ancillary to residential use
- (xiv) Starred hotels
- (xv) Clubs/community Centres
- (xvi) Communication Towers
- (xvii) Guest/Boarding Houses
- (xviii) Any other use, which the Government may in public interest decide

II COMMERCIAL ZONE

- (i) Retail Trade.
- (ii) Wholesale Trade.
- (iii) Warehouses and storages.
- (iv) Commercial offices and banks.
- (v) Restaurant and Transient Boarding Houses including public assistance institutions providing residential accommodation like Dharamshala, Tourist House etc.
- (vi) Cinemas, Hotels, Motels and other places of public assembly like theatres, club, Dramatic Club, etc. run on commercial basis.
- (vii) Professional establishments.
- (viii) Residences on the first and higher floors.
- (ix) Local service industry.
- (x) Public utility buildings.
- (xi) Fuel stations and service garages.
- (xii) Loading and unloading yards.
- (xiii) Parking spaces, bus stops, taxis, tonga and rickshaw stand.
- (xiv) Town parks.
- (xv) Communication Towers
- (xvi) Any other use which the Government in public interest may decide.

III INDUSTRIAL ZONE

- (i) Light industry
- (ii) Medium industry
- (iii) Obnoxious and Hazardous Industry
- (iv) Heavy industry
- (v) Service industry
- (vi) Warehouse and storages
- (vii) Parking, loading and unloading area
- (viii) Truck stand/bus stops, taxi, tonga and rickshaw stand
- (ix) Public utility, community buildings, retail shops, banks, dhabas, restaurants, two/three star hotels and insurance offices subject to a maximum limit of 3 percent of the total area of the sector as under:

Serial	Name of	A	rea	No. of Commercial	Maximum	Floor Area	Approach Road	
number	Facility	Minimum	Maximum	facilities	component	Ground Coverage	Ratio	
1	Dhabas	500 sq m	1000 sq m	2	50 sq m	40 %	0.40	Minimum 18 metres
2	Restaurants	1000 sqm	2000 sq m	2	10 %	30 %	1.50	Minimum 18 metres
3	Two/ Three Star Hotels	1.0 Acre	2.5 Acres	2	15 %	30 %	As per commercial policy	Minimum 24 metres
4	Five Star Hotels	2.5 Acres	4.0 Acres	1	15 %	30 %	As per commercial policy	Sector Dividing Road with the provi-sion of a service road

- (x) Fuel stations and service garages.
- (xi) Liquid Petroleum Gas godowns permitted by the Director.
- (xii) Cyber Parks/Information Technology Parks/ Information Technology Industrial Units
- (xiii) Health Facilities like Hospital, Dispensary, Nursing Home, Clinic as under: -

Serial	Name of	Area		No. of	Residential	Maximum	Floor	
number	Facility	Minimum	Maximum	facilities in a sector	component	Ground Coverage	Area Ratio	
1	Hospital	2.5 Acres	5.0 Acres	1	15 %	33 %	100 %	
2	Dispensary	1.0 Acre	1.5 Acres	1	15 %	33 %	100 %	
3	Nursing Home	250 sq. m	500 sq. m	2	Nil	60 %	100 %	
4	Clinic	250 sq. m	500 sq. m	2	Nil	60 %	100 %	

- (xiv) Industrial Colony with a minimum area of 15 acres. The area utilization shall be as per policy issued *vide* ACS,T and CP, Hry and memo no. 388/PA(RB)/2015/7/16/2006-2TCP dated 01.10.2015 and as amended upto date.
- (xv) Communication Towers
- (xvi) Ready mix concrete plant, wet mix plants, hot mix plants.
- (xvii) Weighing Bridge
- (xviii) Service Garage, Sale/Display Centre-cum-service garage as under:

Serial	Name of	Area (in acres)		Commercial	Maximum	Floor	Approach	Height
number	facility	Minimum	Maximum	component	ground coverage	Area Ratio	Road	
1	Service Garage	0.5	1	Nil	60%	1.25	Minimum 18 metres or service road along sector road	18 metres
2	Sale/Display Centre-cum- service garage	0.5	2	10% of permissible Floor Area Ratio	60%	1.25	Minimum 18 metres or service road along sector road	18 metres

Note: * The fee and charges on commercial component shall be levied on the commercial rates;

- * Existing/already CLU granted service garages shall be considered for grant of permission for sale/display centre subject to fulfillment of the above norms.
- (xix) Any other use, which the Government may in public interest decide.

IV TRANSPORT AND COMMUNICATION ZONE

- (i) Railway yards, railway station and siding.
- (ii) Transport Nagar, Roads and Transport depots and parking areas.
- (iii) Airports and Air Stations.
- (iv) Telegraph offices and Telephone exchange.
- (v) Broadcasting stations.
- (vi) Television station.
- (vii) Agricultural, horticulture and nurseries at approved sites and places.
- (viii) Fuel stations and service garages.
- (ix) Parking spaces, bus stop-shelters, taxi, tonga and auto/ rickshaw stands.
- (x) Logistics Hubs/Container Yards, In land container Depot, Container Freight Station.
- (xi) Communication Towers.
- (xii) Weighing Bridge.
- (xiii) Warehouses upto a maximum limit of 20% of the total area of the sector.
- (xiv) Dhabas, as per prevailing policy.

V PUBLIC UTILITIES

- (i) Water supply installations including treatment plants.
- (ii) Drainage and Sanitary installations including sewage treatment plants and disposal works.
- (iii) Electric Power plant and sub-station including grid sub-station.
- (iv) Gas installations and Gas works.
- (v) Solid Waste management Sites.

VI PUBLIC AND SEMI PUBLIC USES ZONE

- (i) Government offices, Government Administration centres, secretariats and police station.
- (ii) Educational, cultural and religious institutions.
- (iii) Medical health institutions.
- (iv) Civic/cultural and social institutions like theatres, opera houses etc. of predominantly noncommercial nature.
- (v) Land belonging to defence.
- (vi) Communication Towers.
- (vii) Dhabas, Restaurants as under: -

Serial Name of		Area		No. of	Commercial	Maximum	Floor
number	Facility	Minimum	Maximum	facilities	component	Ground	Area
				in a sector		Coverage	Ratio
1	Dhabas	500 sq. m	1000 sq. m	2	50 sq. m	50 %	40 %
2	Restaurants	1000 sq.	2000 sq. m	2	10 %	30 %	150 %
		m					

- (viii) Fuel Stations
- (ix) Any other use which Government in public interest may decide.

VII OPEN SPACES

- (i) Sports ground, stadium and play grounds.
- (ii) Parks and green belts, garden and other recreational uses.
- (iii) Cemetreies crematories etc.
- (iv) Fuel stations, bus queue shelter along roads with the permission of Director.
- (v) Public utility services like electric grid station, transmission lines, communication lines, water supply lines, sewerage lines, drainage lines in the green belts along the scheduled roads and major roads.
- (vi) Communication Towers.
- (vii) Water bodies/ Lakes/water recharge zone.
- (viii) Mela Ground and Multipurpose Ground.
- (ix) Any other use which the Government may in public interest decide.

VIII AGRICULTURE ZONE

- (i) Agricultural, Horticultural, dairy and poultry farming.
- (ii) Village houses within Abadi-deh
- (iii) Farm houses outside abadi-deh subject to restriction as laid down in zoning regulation XIX

- (iv) Educational Institutions
- (v) Afforestation development of any of the part for recreation.
- (vi) Expansion of existing village contiguous to abadi-deh if undertaken a project approved or sponsored by the Central Government, or State Government
- (vii) Milk chilling station and pasteurisation plant
- (viii) Bus Stand and railway station
- (ix) Air ports with necessary buildings
- (x) Wireless stations
- (xi) Grain godowns, storage space at sites approved by the Director
- (xii) Weather stations
- (xiii) Land drainage and irrigation, hydroelectric works and tubewell for irrigation
- (xiv) Telephone and electric transmission lines and poles
- (xv) Mining and extraction operations including lime and brick kilns, stones, quarries and crushing subject to the rules and at approved site
- (xvi) Cremation and burial grounds
- (xvii) Fuel station and service garages
- (xviii) Renewable and non-renewable energy power plants
- (xix) Liquid Petroleum Gas storage godowns with the approval of the Director.
- (xx) Small Scale Industrial units shall be allowed subject to fulfillment of the following conditions, provided that the site should not fall within restricted belt notified under the 'Works Defence Act, 1903' around Defence installations, if any:

A. Si	ting norms							
Zone	Norms							
Medium	Within 2 kms from Urbanisable Zone	Beyond 2 kms from Urbanisable Zone						
potential zone	(excluding the peripheral roads, if	(excluding the peripheral roads, if proposed						
	proposed along urbansiable boundary) along urbansiable boundary)							
	SSI Non-polluting green, orange category units of any area units up to 5 acres							
B. A	pproach norms							
Medium		ad be considered for grant of CLU permission						
Potential zone		ever, in case industrial Change of Land Use						
		7.5 ft) wide revenue rasta/public road, then						
		aid road, shall be considered subject to the						
	condition that the project proponent donates 1 karam (5.5 ft) wide strip of the applied land							
		ough Hibbanama/gift deed so as to make the						
	approach 6 karma (33 ft) in front of the appli	ied site.						

(xxi) Non polluting Medium and Large Scale Agro-based Industries on Public road/rasta not less than 30 feet wide other than scheduled roads, National Highway and State Highway subject to the condition that site should not fall within restricted belt around the defence installation as applicable for such installation if any.

(xxii) Dhabas, Banquet Hall, Small Restaurants, Motels, Hotels, Resort and Amusement Park/ Theme Park along National Highway / Scheduled Roads in the area outside restricted/ green belt as under:

Serial	Serial Permissible Activity		ea	Commercial	Maximum Ground	Floor Area	
number		Minimum	Maximum	Component	Coverage	Ratio	
1	Dhabas	1000 sq.	1 acre	50 Sqmt.	40%	40%	
	/	meters					
2	Restaurant	2000 sq.	1 acre	15%	30%	150%	
		meters					
3	Motel with banquet	2.5 acres	5 acres	15%	30%	150%	
	facilities						
4	Resort	4 acres	10 acres	15%	30%	150%	
5	Amusement Park/Theme	2.5 acres	10 acres	15%	30%	50%	
	Park						

Provided the access permission is obtained from National Highway Authority of India if the site is located on National Highway, and from Executive Engineer, Public Works Department (Building and Roads) if the site is located on scheduled road.

(xxiii) Banquet Hall as per the following norms:-

Permissible Zone	Agriculture Zone			
Approach	1. Minimum width of the approach road must be 18 meters			
	2. The access permission is required from XEN, PWD (B&R) if the site			
	is located on scheduled road.			
	3. Approach from National Highways can be considered, if the site			
	fulfills minimum distance norm from intersection/access and is located			
	on minimum 7 meters wide service road or the applicant submits prior			
	permission of access from NHAI			
Area Required	Minimum area :- 2.5 acres			
	Maximum area :- 5.00 acres			
FAR	50%			
Ground Coverage	30%			
Conversion Charges	50% of the rates prescribed for Commercial use			
Permissible Ancillary uses	10% of the allowed FAR for Gift Shop, STD Booth, Toy Centre and			
within FAR	Flower Shops etc.			
Parking	Minimum 25% of the site area.			

Note: The provision of marriage palace/Banquet Hall within the Municipal Limit shall be as per the policy approved by the Department of Urban Local Bodies and as amended from time to time.

- (xxiv) Microwave Towers/Stations, Seismic Centers and Telecommunication Centers
- (xxv) Communication Towers.
- (xxvi) Ready mix concrete Plants, Wet Mix Plants, Hot Mix Plants connected with the projects for which contract or work is assigned by Government or Government agency and to be set up on short term basis.

(xxvii) Weighing Bridge.

(xxviii) Service Garage, Sale/Display Centre-cum-service garage as under:

Serial	` ,	Commercial	Maximum	Floor	Approach	Height		
number	facility	Minimum	Maximum	component	ground coverage	Area Ratio	Road	
1	Service Garage	0.5	1	Nil	60%	1.25	Minimum 18 metres or service road along sector road	18 metres
2	Sale/Display Centre-cum- service garage	0.5	2	10% of permissible Floor Area Ratio	60%	1.25	Minimum 18 metres or service road along sector road	18 metres

Note: * The fee and charges on commercial component shall be levied on the commercial rates;

- * Existing/already CLU granted service garages shall be considered for grant of permission for sale/display centre subject to fulfillment of the above norms.
- (xxix) Any other use, which Government may in Public Interest, decides.

IX Natural Conservation Zone/Reserved Pocket/Yet to be determined Pocket:

- (i) Agriculture and Horticulture.
- (ii) Pisiculture.
- (iii) Social Forestry / Plantations including afforestation.
- (iv) Regional recreational activities with no construction exceeding 0.5% of the area with the permission of the competent authority.

X USES STRICTLY PROHIBITED:

Storage of Petroleum and other inflammable material without proper license.

APPENDIX -1

Categories of Industries included in the scope / definition of Information Technology Industry

(A) Computing Devices including

Desktop

Personal Computer

Servers

Work-station

Nodes

Terminals

Network P.C

Home P.C.

Lap-top Computers

Note Book Computers

Palm top Computer/PDA

(B) Network Controller Card/ Memories including

Network Interface Card (NIC)

Adaptor Ethernet /PCI/EISA/Combo/PCMICA

SIMMs Memory

DIMMs Memory

Central Processing Unit (CPU)

Controller SCSI/Array

Processors Processor/Processor Power Module/Upgrade

(C) Storage Units including

Hard Disk Drives/Hard Drives

RAID Devices and their Controllers

Floppy Disk Drives

C.D. ROM Drives

Tape Drives DLT Drives/DAT

Optical Disk Drives

Other Digital Storage Devices

(D) Other

Key Board

Monitor

Mouse

Multi-media Kits

(E) Printers and Output Devices including

Dot matrix

Laserjet

Inkjet

Deskjet

LED Printers

Line Printers

Plotters

Pass-book Printers

(F) Networking products including

Hubs

Routers

Switches

Concentrators

Trans-receivers

(G) Software including

Application Software

Operating system

Middleware/Firmware

(H) Power supplies to Computer Systems including

Switch Mode Power Supplies

Uninterrupted Power supplies

(I) Networking/Cabling and related accessories

(related to IT Industry)

Fibre Cable

Copper Cable

Cables

Connectors, Terminal Blocks

Jack Panels, Patch Cord

Mounting Cord/Wiring Blocks

Surface Mount Boxes

(J) Consumables including

C.D.ROM /Compact Disk

Floppy Disk

Tapes DAT/DLT

Ribbons

Toners

Inkjet Cartridges

Inks for Output devices

(K) Electronic Components

Printed Circuit Board/Populated PCB

Printed Circuit Board/PCB

Transistors

Integrated Circuits/ICs

Diodes/Thyristor/LED

Resistors

Capacitors

Switches (On/Off, Push button, Rocker, etc.)

Plugs/sockets/relays

Magnetic heads, Print heads

Connectors

Microphones/Speakers

Fuses

(L) Telecommunication Equipment including:

Telephones

Videophones

Fascimile machines/Fax cards

Tele-Printers/Telex machine

PABX/EPABX/ RAX/MAX Telephone Exchange

Multiplexers/Muxes

Modems

Telephone answering machines

Telecommunication Switching Apparatus

Anetna and Mast

Wireless datacom equipment

Receiving equipments like Pagers, mobile/Cellular Phones, etc.

VSATs

Video Conferencing Equipments

* Including Set Top Boxes for both Video and Digital Signaling.

(M) IT Enabled Services are business processes and services, the end products/services of which are:-

- Delivered outside India.
- Delivered over communication network., and
- Either externally contracted (out-sourced) or provided by a remote subsidiary of the same company (out-located).

Note: Services which would not be included are:-

- Remote production/manufacturing units
- The Corporate offices of companies or their local branches
- Virtual business on Internet.

The following services which meet the above criteria would be included:-


- (i) Back-Office Operations
- (ii) Call Centres
- (iii) Content Development or Animation
- (iv) Data Processing
- (v) Engineering and Design
- (vi) Geographic Information System Services
- (vii) Human Resource Services
- (viii) Insurance Claim Processing
- (ix) Legal Database
- (x) Medical Transcription
- (xi) Payroll
- (xii) Remote Maintenance
- (xiii) Revenue Accounting
- (xiv) Supports Centres and
- (xv) Web-site Services.

S. N. ROY,

Additional Chief Secretary to Government Haryana, Urban Local Bodies Department.

A. K. SINGH,

Principal Secretary to Government Haryana, Town and Country Planning Department.



8797—C.S.—H.G.P., Pkl.